

BETWEEN THE BOTTOM OF THE SOIL ABSORPTION SYSTEM AND THE

20 MINUTES PER INCH).

-2" MIN. DIFFERENCE IN ELEVATION BETWEEN THE DBOX OUTLET AND INLET INTO THE PRESBY PIPE

D-BOX CONNECTION DETAIL SCALE: NOT TO SCALE

HIGH GROUND WATER ELEVATION TO 3 FEET. (SOIL PERCOLATION RATE

SCHEDULE OF ELEVATIONS

INVERT @ FOUNDATION	101.26" EXISTING
INVERT @ SEPTIC TANK IN	101.06' EXISTING
INVERT @ SEPTIC TANK OUT	101.80' EXISTING
INVERT @ D-BOX IN	101.25'
INVERT @ D-BOX OUT	101.08'
INVERT @ PRESBY PIPE	99.91'
BOTTOM OF PRESBY PIPE	99.33'
TOP OF PRESBY PIPE	100.33'
BOTTOM OF SYSTEM SAND	98.83'
DESIGN ELEVATION	98.33'
GROUNDWATER ELEVATION	95.83'
BREAKOUT ELEVATION	98.83'
FINISHED GRDE OVER S.A.S	101.33'


DESIGN INFORMATION DESIGN FLOW = 440 G.P.D. 4 BEDROOMS X 110 G.P.D. = 440 DESIGN PERCOLATION RATE = 20 M.P.I. CLASS II SOIL 4 BEDROOM HOUSE @ 20 MPI REQUIRES 200 L.F. OF PRESBY SEPTIC PIPE PROPOSED SYSTEM PROVIDES 5 LINES @ 40' TOTAL OF 200 L.F. SAS SLOPE IS 0% REQUIRES MIN. 1.50' O.C. SPACING, SPACE LINES @ 2.25' O.C. **LEACHING AREA PROVIDED:** BED AREA REQUIRED FOR CONVENTIONAL SYSTEM IS 833 S.F.


40% REDUCTION FOR PRESBY ENVIRO SEPTIC SYSTEM IS 500 S.F. PROPOSED SYSTEM BED IS 42' L X 12' W = 504 S.F. OF BED AREA 504 S.F IS > 500 S.F. O.K.

PROVIDE:

1 FIELD 42'L X 12'W = 504 S.F. OF C-33 SYSTEM SAND 5 LINES 40' LONG 2.25' O.C. OUTSIDE EDGE OF PIPE #1 - #5 = 10' PROVIDE 1 FOOT OF C-33 SAND AROUND EDGE OF PRESBY PIPE. **USE A SERIAL SYSTEM**

TYPICAL SERIAL SYSTEM





LEGEND				
PROPERTY LINE				
DEEP HOLE TEST				
PERC HOLE TEST				
WELL O	İ			
EXISTING CONTOURS				
PROPOSED CONTOURS				
EDGE OF WETLAND				
HAYBALES				
SILTFENCE ***********************************				
WATER LINE				
WETLAND FLAG 区				
TREE, SOFTWOOD SW12IN	-			
TREE, HARDWOOD HW12IN				



GENERAL NOTES

ALL MODIFICATIONS TO THIS PLAN MUST BE PRE-APPROVED IN WRITING BY THE DESIGN ENGINEER AND THE LOCAL

THE INSTALLER SHALL HAVE A CURRENT, VALID INSTALLERS PERMIT ISSUED BY THE LOCAL BOARD OF HEALTH IN THE

TOWN THE WORK IS PROPOSED.

ALL SYSTEM SAND SHALL BE WASHED AND THE INSTALLER SHALL PROVIDE TO THE BOH DOCUMENTATION OF A SIEVE ANALYS ON ALL SAND USED IN THE INSTILLATION OF THE SYSTEM.

ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS OF TITTLE 5 AND THE LOCAL BOARD OF HEALTH.

THREE INSPECTIONS BY THE DESIGN ENGINEER AND THE LOCAL BOARD OF HEALTH SHALL BE REQUIRED TO OBTAIN A CERTIFICATE OF COMPLIANCE. 1. BOTTOM INSPECTION FOR THE REMOVAL OF TOP AND SUBSOIL, AND ANY UNSUITABLE MATERIAL, 2. COMPONENT INSPECTION INCLUDING BUT NOT LIMITED TO SEPTIC TANK, PUMP CHAMBER, DISTRIBUTION BOX, SOIL ABSORBTION SYSTEM, BUILDING SEWER AND ANY OTHER COMPONENTS USED IN THE CONSTRUCTION OF THE SYSTEM, 3. FINAL GRADING AND SOIL STABILIZATION INSPECTION

HEAVY EQUIPMENT OR ANY OTHER MACHINERY THAT MAY CRUSH OR DISTURB THE SYSTEM SHALL NOT BE ALLOWED

THE SYSTEM WAS NOT DESIGNED TO FACILITATE A GARBAGE DISPOSAL.

REQUIREMENTS OF THE LOCAL BOARD OF HEALTH.

TOPSOIL, SUBSOIL, FILL, OR ANY OTHER UNSUITABLE MATERIALS SHALL BE REMOVED FROM THE AREA OF THE SOIL ABSORBTION SYSTEM AND FOR A DISTANCE OF 5 FEET ON ALL SIDES OF THE SAS.

WHERE A SOIL ABSORBTION SYSTEM IS TO BE CONSTRUCTED IN FILL, THE FILL SHALL BE PLACED IN 12 INCH LIFTS AND COMPACTED OR ALLOWED TO SETTLR FOR 1 YEAR. THE FILL SHALL CONFORM TO TITTLE 5 SPECIFICATIONS AND THE

THE BASE FOR THE SEPTIC TANK, PUMP CHAMBER, AND DISTRIBUTION BOX SHALL BE PLACED ON A FIRM AND LEVEL BASE OF 6" OF CRUSHED STONE, AND SHALL BE COMPACTED BY A VIBRATORY TAMPER OR EQUAL.

ALL INTERIOR PLUMBING SHALL BE CONNECTED TO THE PROPOSED SEPTIC SYSTEM.

BACKWASH FROM WATER SOFTENING, CONDITIONING AND FILTRATION SYSTEMS SHALL NOT BE DISCHARGED TO THE

THE FOUR CORNERS OF THE SYSTEM SHALL BE STAKED BY THE CONTRACTOR TO FACILITATE THE FINAL GRADING

ALL WETLAND RESOURCES WITHIN 150 FEET OF THE SYSTEM ARE SHOWN ON THE PLAN.

ALL WELLS WITHIN 150 FEET OF THE SYSTEM ARE SHOWN OR NOTED ON THE PLAN.

ALL APPLICABLE STATE AND LOCAL PERMITS SHALL BE OBTAINED PRIOR TO THE START OF CONSTRUCTION.

HYDROLIC CEMENT IS REQUIRED TO SEAL ALL CONNECTIONS TO THE TANK, PUMP CHAMBER AND DISTRIBUTION BOX.

PROPERTY LINES ARE BASED ON RECORDED DOCUMENTS AND FIELD OBSERVATIONS. THE LOT DOES NOT LIE WITHIN A FLOOD PLAIN AS SHOWN ON FLOOD INSURANCE RATE MAPS.

IF FILL OVER THE D BOX IS GREATER THAN 9 INCHES A RISER MUST BE PROVIDED TO BRING THE D BOX WITHIN 6 INCHES

IT IS RECOMMENDED THAT THE SYSTEM BE PUMPED EVERY 2 YEARS AND A MAINTAINANCE INSPECTION IS PERFORMED

ALL COMPONENTS SHALL BE MARKED WITH MAGNETIC TAPE. THE TAPE SHALL BE OF PROPER RATING TO LOCATE

THE CONTRACTOR SHALL INSTALL A MINIMUN OF ONE INSPECTION PORT IN THE SAS. THE PORT SHALL BE 4 INCH PERFERATED SCH.40 PIPE WITH A SCREW CAP. THE TOP OF THE PORT SHALL BE A MAXIMUM 3 INCHES BELOW GRADE AND EXTEND TO THE TOP OF THE SYSTEM SAND.

ALL SYSTEM PIPING SHALL BE SCHEDULE 40.

COMPONENTS AT THE PROPOSED DEPTH.

SOIL TESTING RESULTS

DATE OF TEST: 6/30/05 TEST PERFORMED BY: WILLIAM COYLE WITNESS: EARL BERNIER LEICESTER B.O.H. PERC # 1- 12 MPI, PERC # 2- 20 MPI

SOIL LOGS

DEEP	HOLE	E#1	ELEV.	98.0
0-5	Α	SL	10 YR 3/3	
5-26	Bw	SL	10 YR 4/4	
26-82	C	SL	2.5 Y 5/3	

I CERTIFY THAT I AM CURRENTLY APPROVED BY THE

EVALUATIONS AND THAT THE ABOVE ANALYSIS HAS

DEPARTMENT OF ENVIRONMENTAL PROTECTION

PURSUANT TO 310 CMR 15.017 TO CONDUCT SOIL

BEEN PERFORMED BY ME CONSISTENT WITH THE

REQUIRED TRAINING, EXPERTISE, AND EXPERIENCE

DESCRIBED IN 310 CMR 15.017. I FURTHER CERTIFY

THAT THE RESULTS OF MY SOIL EVALUATION, AS INDICATED ON THE ATTACHED SOIL EVALUATION

FORM, ARE ACCURATE AND IN ACCORDANCE WITH

310 CMR 15.100 THROUGH 51.107.

REDOX @ 30"

30-80 C SL

REDOX @ 32"

DEEP HOLE #2 ELEV. 96.22'

7-30 Bw SL 10 YR 4/4

2.5 Y 5/3

PREPARED FOR

TRISHA TARENTINO 5 HEMLOCK ST. LEICESTER MA. 01524

WAYNE J. CURRAN R.S.

ENVIRONMENTAL CONSULTANT 34 SHERBROOK AVENUE WORCESTER, MA 01604 (508) 864-4203

PERC TESTS **SOIL EVALUATIONS** SYSTEM DESIGN WETLAND DELINEATION **ENVIRONMENTAL CONSULTING**

PROPOSED SEPTIC SYSTEM REPAIR

5 HEMLOCK ST.

LEICESTER, MA

PLAN DATE **JUNE 17, 2021**