
SITE DEVELOPMENT PLAN SOLAR ENERGY STORAGE SYSTEM (ESS) 1355 MAIN STREET IN LEICESTER, MASSACHUSETTS SEPTEMBER 21, 2021



APPLICANT:

ZP BATTERY DEVCO, LLC BRENDON GOVE 10 E. WORCESTER STREET, SUITE 3A WORCESTER, MASSACHUSETTS 01604

OWNER:

WR ENTERPRISES, LLC 1323 MAIN STREET LEICESTER, MASSACHUSETTS 01420


CIVIL ENGINEER & LAND SURVEYOR:


HANNIGAN ENGINEERING, INC. 8 MONUMENT SQUARE LEOMINSTER, MASSACHUSETTS 01453 TEL: (978) 534-1234


PLAN INDEX


SHEET	1	LOCUS PLAN
SHEET	2	INDEX PLAN
SHEET	3	EXISTING CONDITIONS PLAN
SHEET	4	SITE DEVELOPMENT PLAN
SHEETS	5-6	CONSTRUCTION DETAILS

PERMITTING SET - NOT FOR CONSTRUCTION









EROSION & SEDIMENTATION CONTROL PLAN

THE PURPOSE OF THIS PLAN IS TO PRESENT A PREVENTIVE METHOD OF CONSTRUCTION TO MINIMIZE THE IMPACT OF THE CONSTRUCTION ACTIVITIES UPON WETLAND AND OTHER SENSITIVE AREAS. THE DATA CONTAINED ON THIS PLAN IS INTENDED TO SUPPLEMENT THE DEVELOPER OR CONTRACTORS' EXPERTISE AND IS NOT MEANT TO CIRCUMVENT LOGICAL DECISIONS REQUIRED BY A VARIETY OF FIELD CONDITIONS NCLUDING WEATHER AND THE TYPE OF EQUIPMENT AVAILABLE TO THE

THE CONTRACTOR IS TO BE AWARE OF THE REQUIREMENTS AND OBLIGATIONS TO COMPLY WITH CHAPTER 131, SECTION 40 OF THE MASSACHUSETTS GENERAL LAWS, OTHERWISE KNOWN AS THE WETLANDS PROTECTION ACT, AND ITS ASSOCIATED REGULATIONS (310 CMR 10.00). CERTAIN PERMITS IN THE FORM OF AN ORDER OF CONDITIONS, OR OTHER FORMAT, MAY BE REQUIRED FOR THE CONSTRUCTION AS DEPICTED ON THIS PLAN. THESE PERMITS SHALL BE REVIEWED AND ADHERED TO BY THE CONTRACTOR THROUGHOUT THE CONSTRUCTION PROCESS. THE CONTRACTOR SHALL ALSO MAINTAIN COPIES OF ALL PERMITS ON SITE

3. IF CHANGES IN THE PROJECT ARE REQUIRED DUE TO FIELD CONDITIONS THE DEVELOPER/CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER FOR REVIEW OF THESE CONDITIONS. UPON REVIEW, AND PRIOR O THE IMPLEMENTATION OF ANY CHANGE, THE CONTRACTOR AND THE NGINEER SHALL MEET WITH THE APPROPRIATE LOCAL AND/OR STATE OFFICIAL. OR ITS AGENT. TO DETERMINE IF THE CHANGE RÉQUIRES MODIFICATION TO EXISTING APPROVED PERMITS.

ALTERATION AND/OR DESTRUCTION OF WETLAND AREAS WITHOUT PRIOR CONSENT OF THE CONSERVATION COMMISSION IS PROHIBITED. SILTATION PLUMES, ILLICIT DISCHARGES, OR INADVERTANT ALTERATION SHALL BE CONSIDERED AS ACTIVITIES NOT PERMITTED BY THE ORDER AND SHALL BE REPORTED TO THE CONSERVATION COMMISSION ALONG WITH THE PROPOSED MITIGATIVE MEASURES.

PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, THE EROSION AND SEDIMENT CONTROL BARRIER SHALL BE INSTALLED AS SHOWN ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN THE EROSION CONTROL BARRIER UNTIL ALL WORK IS COMPLETE AND ALL AREAS HAVE BEEN STABILIZED. THE REMOVAL OF SEDIMENT CONTROL DEVICES SHALL BE ONLY UPON THE APPROVAL OF THE CONSERVATION COMMISSION.

S. EROSION AND SEDIMENTATION CONTROL DEVICES, SUCH AS CHECK DAMS, SEDIMENT BASINS, ETC. ARE TO BE INSTALLED AS SHOWN ON THE SITE DEVELOPMENT PLANS WITH ASSOCIATED DETAILS, AS APPROPRIATE.

CONSTRUCTION OPERATIONS SHALL NOT CAUSE NOTICEABLE SEDIMENTATION PLUMES TO OCCUR ON OR SURROUNDING THE PROJECT. SHOULD SEDIMENT EXTEND BEYOND THE EROSION CONTROL BARRIERS, THE CONTRACTOR SHALL STOP WORK AND INSTALL ADDITIONAL MITIGATION MEASURES TO PREVENT FURTHER SEDIMENTATION.

NO MATERIAL SUBJECT TO EROSION SHALL BE STOCKPILED OVERNIGHT WITHIN 100 FEET OF ANY WETLAND AREAS WITHOUT PROPER EROSION AND SEDIMENTATION DEVICES IN PLACE.

EQUIPMENT SHALL NOT BE PARKED WITHIN WETLAND OR BUFFER AREAS EXCEPT DURING ACTUAL OPERATIONS REQUIRING SAID EQUIPMENT. D. ACCUMULATED SEDIMENT ALONG EROSION CONTROL BARRIERS SHALL

BE PERIODICALLY REMOVED AND DISPOSED OF BY THE CONTRACTOR AS REQUIRED BY THE CONSERVATION COMMISSION OR AS DIRECTED BY THE

<u>EROSION CONTROL METHODS:</u>

IT IS OF GREAT IMPORTANCE THAT CONCENTRATION OF RUNOFF BE AVOIDED IN ORDER TO PREVENT THE TRANSPORT OF SEDIMENT. THE PRIMARY EROSION CONTROL METHOD TO BE UTILIZED IS TO LIMIT THE AREA OF DISTURBANCE DURING CONSTRUCTION ACTIVITIES. THIS IS ACCOMPLISHED BY PROMPT STABILIZATION OF DISTURBED AREAS UPON COMPLETION OF SEQUENCES OF CONSTRUCTION.

EROSION AND SEDIMENT CONTROL DEVICES SUCH AS HAY BALES, SILT FENCES, DIVERSION BERMS, ETC. SHALL BE UTILIZED FOR THE PROTECTION OF THE AREAS BEYOND THE LIMIT OF CONSTRUCTION.

<u>DEMARCATION OF SENSITIVE AREAS:</u>

IT IS RECOMMEND THAT BARRIERS BE PLACED ON THE SITE TO CONTROL THE LIMITS OF THE DISTURBANCE. AS AN EXAMPLE, HAY BALE BARRIERS PROVIDE SUCH DEMARCATION AND OTHER METHODS SUCH AS LOG BARRIERS, ROPE WITH FLAGGING, ETC. MAY BE UTILIZED. CARE SHOULD BE TAKEN IN THE OPERATION OF EQUIPMENT, SUCH HAT ONLY THE MINIMUM AREA NEEDED TO BE ALTERED IS DISTURBED.

ACCESS TO THE SITE SHALL BE MADE IN THE AREA OF A PERMANENT DRIVEWAY OR ROADWAY UNLESS DOING SO WOULD RESULT IN A TRAFFIC

2. AN AREA OF CRUSHED STONE SHALL BE PLACED AT THE DRIVEWAY ENTRANCE TO INSURE THAT MUD IS NOT TRACKED ONTO THE EXISTING ROAD (SEE CONSTRUCTION ENTRANCE DETAIL). IF MUD IS INADVERTENTLY TRACKÈD ONTO THE ROAD, IT SHOULD BE PROMPTLY REMOVED.

LABORERS VEHICLES SHALL BE PARKED IN A DESIGNATED AREA AS O MINIMIZE DISTURBED SURFACES AND TO INSURE THAT RUTS ARE NOT CREATED AND WHICH COULD CARRY WATER TO A WETLAND OR OTHER

SUITABLE MEASURES SHALL BE TAKEN TO INSURE THAT LARGE DELIVERY TRUCKS SERVICING THE SITE DO NOT DAMAGE TO AREAS OF EXISTING VEGETATION OR CAUSE DISTURBANCE TO STABILIZED AREAS.

ORDERLY CONSTRUCTION PROCEDURES:

THE CONTRACTOR SHALL PERFORM SITE CONSTRUCTION IN A MANNER WHICH WILL INSURE THE STABILIZATION OF AREAS IN PROXIMITY OF OR TRIBUTARY TO WETLAND AREAS AS SOON AS POSSIBLE.

2. EROSION CONTROL DEVICES SUCH AS HAY BALE BARRIERS, SILT FENCES AND MULCH SHALL BE BROUGHT TO THE SITE AND STOCKPILED PRIOR TO INITIATING CONSTRUCTION.


THE CONTRACTOR SHALL PROVIDE AREAS FOR THE TEMPORARY STORAGE OF CONSTRUCTION DEBRIS. CONSTRUCTION DEBRIS SHALL NOT BE ALLOWED TO ACCUMULATE FOR AN EXTENDED PERIOD OF TIME.

LAND CLEARING SHALL BE PERFORMED IN PHASES CONSISTENT WITH

ACTUAL CONSTRUCTION REQUIREMENTS. FINAL LAND CLEARING SHALL BE LIMITED TO RETURN TO GRADE SLOPES. . TREES SHALL BE CUT FOR ENTIRE SITE LEAVING SUMPS IN PLACE TO

MAINTAIN SOIL STABILIZATION. 3. STUMPS SHALL BE PULLED AND STOCKPILED FOR GRINDING. 1. BRUSH AND BRANCHES SHOULD BE CHIPPED AND UTILIZED FOR WOOD MULCH IF PRACTICAL.

5. VEHICLES UTILIZED IN THE CLEARING OPERATION SHOULD NOT TRAVERSE WETLANDS OR FLOWING BROOKS OR STREAMS WITHOUT PRIOR APPROVAL FROM THE LOCAL CONSERVATION COMMISSION OR AGENT.



PERIMETER SIGNAGE NO SCALE

12" x 9" SIGNS TO BE PLACED ALONG FENCELINE AT 50 FT INTERVALS

ROUGH GRADING:

. THE ROUGH GRADING OF THE SITE SHALL FOLLOW THE FILL AND EXCAVATION SEQUENCES AS DESCRIBED ON THE CONSTRUCTION PHASING PLANS. SLOPES SHALL BE MAINTAINED AWAY FROM WETLANDS AND

SENSITIVE AREAS AS MUCH IS PRACTICAL. 2. DURING THIS PROCESS THE EROSION POTENTIAL IS HIGH. SUFFICIENT EROSION CONTROL BARRIERS SHOULD BE KEPT IN PROXIMITY TO THE WORK AREA TO ALLOW QUICK ACTION SHOULD EROSION BECOME AN ISSUE AND TO INSURE THAT NO SEDIMENT REACHES WETLANDS OR

OTHER SENSITIVE AREAS. 3. IN AREAS OF CUT AND/OR FILL WHERE SLOPES COULD DIVERT WATER TOWARD WETLAND AREAS, DIVERSION TRENCHES AND/OR SWALES SHOULD BE CONSIDERED AND IMPLEMENTED TO DIVERT WATER AWAY

4. STEEP SIDE SLOPES IN EXCAVATION OR FILL SHOULD BE AVOIDED. DISTURBED AREAS SHALL BE STABILIZED BY LOAMING AND SEEDING OR RIPRAPPED IMMEDIATELY AFTER THE FINISH GRADE HAS BEEN MET. IF FINAL GRADING DOES NOT OCCUR DURING THE GROWING SEASON THESE AREAS SHALL BE MULCHED WITH HAY WITH A TACKIFIER, IF NECESSARY SLOPED AREAS MAY REQUIRE ADDITIONAL CONTROLS SUCH AS EROSION CONTROL SOCKS OR HAYBALES.

6. A GROUND COVER SUFFICIENT TO RETAIN SOILS IN A STABILIZED CONDITION MUST BE PROVIDED WITHIN 14 WORKING DAYS, SEASON PERMITTING, ON ANY PORTION OF THE TRACT UPON WHICH FURTHER ACTIVE CONSTRUCTION IS NOT BEING UNDERTAKEN.

1. IF DRAINAGE PIPES OR SWALES ARE TO BE INSTALLED, THEY SHALL BE CONSTRUCTED FROM DOWNSTREAM UP AND CONSTRUCTION SHALL INCLUDE THE PLACEMENT OF OUTFALL RIPRAP AND OTHER MITIGATIVE MEASURES SHOWN ON THE PLAN.

2. PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, HAY BALES OR OTHER SUITABLE METHODS TO ENTRAP SEDIMENT SHALL BE PLACED

3. THE TOE OF EMBANKMENTS SHALL BE STABILIZED IMMEDIATELY, MULCHED AND TACKED DOWN BY SUITABLE MEANS.

CREATION OF DETENTION BASIN:

. THE DETENTION BASIN HAS BEEN PLACED AS A SEPARATE ITEM TO EMPHASIZE THE IMPORTANCE OF EROSION CONTROL DURING ITS

THE PRIMARY EROSION CONTROL METHOD FOR BASIN CONSTRUCTION, AS WELL AS FOR THE SITE IS THE RAPID STABILIZATION OF ALL SURFACES. SECONDARY IN IMPORTANCE IS THE CONCENTRATION OF RUNOFF BE AVOIDED IN ORDER TO PREVENT THE TRANSPORT OF

3. DURING CONSTRUCTION, THE FILL AND EXCAVATION SEQUENCES SHOWN ON THE CONSTRUCTION PHASING PLANS, ALONG WITH THE DETAILS PROVIDED IN THIS PLAN SET SHALL BE UTILIZED. THESE SEQUENCES REQUIRE THAT SLOPED AREAS LEFT FOR ANY PERIOD OF TIME NOT SLOPED TOWARDS THE WETLAND OR SENSITIVE AREA, BUT RATHER BACK INTO THE FILL MATERIAL.

4. THE BASIN BERM IS TO BE CONSTRUCTED BY EQUIPMENT WORKING ON STABLE MATERIAL ONLY. HAY BALES SHALL BE PLACED AT THE TOE OF SLOPE UNTIL SURFACES ARE STABILIZED.

5. NO EXCAVATION WITHIN THE BASIN SHALL COMMENCE UNTIL THE BERM IS IN PLACE.

CARE SHOULD BE TAKEN TO INSURE THAT ORGANIC MATERIAL REMOVED FROM THE BASIN AREA IS RESERVED FOR FINISH GRADING AND THE STABILIZATION OF DISTURBED AREAS.

7. IF DEWATERING IS NECESSARY, PUMPING TO A SETTLING BASIN SHALL BE PERMITTED IF SETTLING BASIN IS CONSTRUCTED, MAINTAINED AND

8. AT NO TIME SHALL RUNOFF CARRYING SEDIMENT BE ALLOWED TO FLOW TO THE WETLANDS OR SENSITIVE AREAS.

9. THE WORK AREA SHALL REMAIN FREE OF LITTER AND DEBRIS AT ALL TIMES AND MONITORED ON A DAILY BASIS TO ENSURE COMPLIANCE. 10. ALL MATERIALS STOCKPILED SHALL BE LOCATED, MULCHED OR OTHERWISE TREATED TO INSURE THAT MATERIALS CONTAINED, THEREIN, AREA NOT CARRIED INTO THE WETLANDS.

11. ANY MATERIALS BLOWN OR CARRIED BY WATER AWAY FROM THE CONSTRUCTION SITE OR INTO THE WETLAND AREAS SHALL BE PROMPTL) REMOVED AS REQUIRED BY THE LOCAL CONSERVATION COMMISSION. 12. A GEOTECHNICAL FILTER FABRIC SHALL BE PLACED OVER THE BASIN SUBDRAIN DURING CONSTRUCTION TO PREVENT SEDIMENT FROM ENTERING AND CLOGGING THE DRAIN. THE FABRIC SHALL BE REMOVED FOR BASIN

<u>GRUBBING AND STRIPPING:</u>


PREPARATION FOR FINAL STABILIZATION.

1. TOP SOIL SHALL BE RETAINED AND STOCKPILED FOR LANDSCAPING PURPOSES.

P. GRUBBING AND STRIPPING OF SLOPES LEADING TO WETLAND AREAS SHOULD NOT BE UNDERTAKEN DURING PERIODS OF INTENSE RAINFALL. 3. TOP SOIL STOCKPILE LOCATIONS ARE DEPICTED ON THE SITE DEVELOPMENT PLAN, THE EROSION CONTROL PLAN, AND/OR THE CONSTRUCTION PHASING PLAN AND SHALL BE ADHERED TO. 4. WHEN WORKING IN THE VICINITY OF WETLANDS, TOP SOIL SATURATED WITH WATER SHALL BE REMOVED, AND CONTAINED PRIOR TO BEING USED. 5. AREAS LEADING TO WETLANDS SHALL HAVE HAY BALE BARRIERS INSTALLED ACROSS THEM IN ARCS POINTING DOWN THE HILL AT INTERVALS SUFFICIENT TO MITIGATE RUNOFF CARRYING SEDIMENT.

6. DURING PERIODS OF INTENSE RAINFALL, OR IF THE PROJECT IS TO BE LEFT FOR A PERIOD OF TIME, CONSIDERATION SHOULD BE GIVEN TO SUPPLEMENT HAY BALE BARRIERS WITH EITHER CRUSHED STONE OR ARMORED BARRIERS. CONSIDERATION MAY ALSO BE GIVEN TO DIVERTING RUNOFF INTO TEMPORARY SEDIMENTATION CONTROL AREAS. 7. WHENEVER PRACTICAL, NATURAL VEGETATION SHALL BE RETAINED, PROTECTED AND SUPPLEMENTED.

, 9ga ALUMINUM WIRE TIES TWISTED SELVAGE TENSION WIRE 2 1/2" DQ40 LINE " DQ40 TERMINAL -CORNER POST 9ga ALUMINUM WIRE TIES @12" APART -BOTTOM TENSION WIRE 9GA WITH 9GA AL HOG RINGS @ TENSION BAR WITH-TENSION BANDS @ 12" 2 1/2" DQ40 LINE POST-CONCRETE FOOTINGS~ " CLEARANCE KNUCKLED SELVAGE



FENCE POST DETAIL

NO SCALE

SECURE THE STRAW WATTLE WITH WOOD STAKES EVERY 3-4 FEET AND WITH A STAKE AT EACH END. STAKES

SHOULD BE DRIVEN THROUGH THE

STAKES SHOULD BE DRIVEN PERPENDICULAR TO THE SLOPE FACE.

SPACING

180 FEET

100 FEET

30 FEET 20 FEET

MIDDLE OF THE WATTLE LEAVING

2-3" OF THE STAKE EXPOSED.

(SEE STRAW WATTLE DETAIL)

SLOPE

FOR PAVEMENT SURFACE TREATMEN (SEE SPECIFICATIONS) (THIS SHEET) INSTALL WARNING AND TRACER WIRE 1. BELOW FINISH GRADE SAND BACKFILL MATERIAL HAND PLACED & COMPACTI IN 6" LIFTS TO 12" ABOVE IRECTLY ABOVE ELECTRICAL LINE FILTER CLOTH TO BE WITHIN 6" OF PIP (WHERE REQUIRED) TO BE PLACED AGAINST <u>CONDUIT TRENCH</u>

SECTION IN SHOULDER

TOLERANT GRASSES

ADJACENT STRAW

TIGHTLY OVERLAP

WATTLE SHALL

- BASED ON SLOPE

GRADIENT

APPLICANT:

BRENDON GOVE

OWNER:

ZP BATTERY DEVCO, LLC

WR ENTERPRISES, LLC

1323 MAIN STREET

10 E. WORCESTER STREET, SUIT 3A

LEICESTER, MASSACHUSETTS 01524

WORCESTER, MASSACHUSETTS 01604

(SEE TABLE)

COLOR OF ALL MATERIALS

INCLUDES 1QTY 20' WIDE DOUBLE GATE

ARE GALVANIZED

GATE POSTS 4"

LINE POSTS 2.5"

TERMINAL POSTS 3"

TOP TENSION WIRE 7ga HOG RINGS WITH STEEL CORE

TENSION BANDS @ 12"

WIRE TO MATCH FABRIC.

BOTTOM TENSION WIRE WITH 9ga AL HOG RINGS

DOME CAPS RAIL ENDS

STEEL CORE GALVANIZED

with 9ga PVC EXTRUDED

COATED STEEL CHAIN LINK

· · ·

* * * *

STRAW

· · · · · · ·

· · · · ·

. . .

`WATTLE


FABRIC AS PER ASTM F668

POLY VINYL CHLORIDE

9ga TIE WIRES WITH STEEL CORE

3" BRACE BANDS

WIRE 9ga TENSION



SWALE DEPTH

(2' AVERAGE)

SWALE DETAIL

NO SCALE — WIDTH VARIES (SEE SITE PLAN) ——— 'FACILITY NAME" SUB-BASE MATERIAL, CLEAN FILL COMPACTED TO 95% DRY DENSITY OWNER CONTACT INFORMATION (###) ### — #### OPERATOR CONTACT INFORMATION (###) ### — ####

STRAW WATTLE DETAIL

EMERGENCY CONTACT INFORMATION

(###) ### - ####

TYPICAL PROJECT SIGN

24" x 24"

SIGNS TO BE PLACED AT ENTRANCE OF PROJECT

TRENCH

FILTER FABRIC

CONSTRUCTION

CLEAN-

ACCUMULATED


REGULARLY

SILT AND DEBRIS

🥆 UNDISTURBED EARTH OR SUITABLE MATERIAL 🖊 COMPACTED TO 95% DRY DENSITY GRAVEL ACCESS LANE SECTION (FOR ACCESS TO SITE AND DETENTION BASIN) NO SCALE

FENCE POST FOR SIDE SLOPES. TWO STAKES/BALE FILTER FABRIC STRAW CONSTRUCTION 12" COMPACTED GRANULAR BASE M1.03.0- TYPE A ANGULAR STONES (50 LB. - 125 LB.) (MHD SPEC. M2.02.3) PLACED TO WETLAND SIDE FORM A COMPACT, STABLE CHANNEL 6" MINIMUM STONED BOTTOM DRAINAGE EDGE OF FABRIC TO PENETRATION BE SECURED IN 6" DEEP TRENCH STRAW BALE WITH SILT FENCE DETAIL

> GRADING REVISIONS CMA 2 11/15/21 1 10/19/2 PEER-REVIEW COMMENT CMANO. DATE BY REVISIONS





8 Monument Square LEOMINSTER, MASSACHUSETTS 01453

(978) 534-6060 (F WWW.HANNIGANENGINEERING.COM


(978) 534-1234 (T

CONSTRUCTION DETAILS LEICESTER, MASSACHUSETTS

PREPARED FOR: ZP BATTERY DEVCO, LLC BRENDAN GOVE

10 E WORCESTER STREET SUITE 3A WORCESTER, MASSACHUSETTS 01604

SCALE: NA CALC: CMA DRWN: CMA APPD: WDH DATE: SEP 21, 202 CHKD: WDH **FB:** 71–22 JOB NO: 3010 SRV: JEF SHEET 5 OF 6 **TAB:** (5-6)DET PLAN NO:C-17-3



AS TOP TRENCH)

PROCEDURES FOR INSTALLATION OF EROSION CONTROL BLANKET: PREPARE SLOPES WITH FINAL GRADING AND LOAM PLACEMENT. RAKE AND ŚMOOTH FINAL SURFACE, APPLY <u>APPLICABLE SEED MIX</u>.

WIDE ANCHOR TRENCH. PLACE BLANKETS, STAPLE (8" STAPLES), BACKFILL AND COMPACT WITH FABRIC OVERLAP OF 12". 3) ROLL BLANKETS DOWN THE SLOPE. STAPLE THE OPEN BLANKET EDGE USING ONE ROW OF STAPLES AT 2' INTERVALS. THE INTERIOR OF THE BLANKET SHOULD BE STAPLED USING A 2' WIDE x 3' HIGH STAPLE PATTERN. BE SURE TO LAY

4) USE AN 6" OVERLAP BETWEEN BLANKET SPLICES. USE A SINGLE ROW OF STAPLES TO ANCHOR BLANKETS TOGETHER.

5) PROVIDE 6"x 6" ANCHOR TRENCH AT TOE OF SLOPE. 6) EROSION CONTROL BLANKET TYPE SHALL BE PROPERLY SELECTED FOR SOIL

7) ANY/ALL METALLIC ANCHORS SHALL BE PROMPTLY REMOVED ONCE THE VEGETATIVE COVER HAS BEEN ESTABLISHED. 8) GRASS SEED VARIETY SHALL BE PROPERLY CHOSEN FOR SPECIFIC SITE

BLANKETS LOOSLY ON THE GROUND ALLOWING A GOOD CONTACT BETWEEN SOIL CONDITIONS AND MAXIMUM ALLOWABLE SLOPE.


EROSION CONTROL SLOPE DETAIL

NO SCALE


BOTTOM TRENCH AND CONDITIONS (SHADE OR SUN, ETC.) ANCHORS (SAME SPACING EROSION CONTROL BANKET PLACEMENT

EROSION


CONTROL BLANKET




NOTE: FOUNDATION FOR BERM CONSTRUCTION SHALL BE CLEARED OF ALL TOP SOIL, ROCKS, DEBRIS, STUMPS, ETC. TO A FIRM SURFACE. IN NO CASE SHALL THIS EXCAVATION BE LESS THAN 12 INCHES SUBGRADE SHALL BE SCARIFIED AND MOISTENED TO A DEPTH OF 3 INCHES PRIOR TO PLACEMENT OF FILL.



DETENTION BASIN BERM (REQUIRED FOR DETENTION BASIN CONSTRUCTION)





PROJECT SIGHT LINE

HORIZONTAL SCALE=1":40' VERTICAL SCALE=1":4'

STORMWATER OPERATION AND MAINTENANCE PLAN

THE FOLLOWING SHALL BE CONSIDERED THE OPERATION & MAINTENANCE PLAN (OMP) FOR THE STORMWATER COLLECTION FACILITY
FOR THIS DEVELOPMENT. THIS OMP HAS BEEN PREPARED IN ACCORDANCE WITH THE STORMWATER MANAGEMENT POLICY AS ISSUED
BY THE DEPARTMENT OF ENVIRONMENTAL PROTECTION.

I. SYSTEM OWNERSHIP
THE SYSTEM SHALL INCLUDE THE DRAINAGE INFRASTRUCTURE AND ALL OF ITS COMPONENTS AS SHOWN ON THE SITE
DEVELOPMENT PLANS, INCLUDING THE DETENTION FACILITIES AND OUTFALL AREAS OF THE DRAINAGE SYSTEM. THE
STRUCTURES OF THE SYSTEM SHALL INCLUDE THE DRAINAGE SWALES AND THE OUTFALL & CONTROL STRUCTURES. THE
SYSTEM SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CONSTRUCTION DETAILS AND THE APPROVED PLANS.

UPON THE COMPLETION OF CONSTRUCTION THE DRAINAGE SYSTEM DESCRIBED ABOVE AND AS DEPICTED ON THE SITE PLANS SHALL BECOME PROPERTY OF THE LAND OWNER, WITH SPECIFIC EASEMENT RIGHTS TO THE OPERATOR OF THE SOLAR SYSTEM TO MAINTAIN THE DRAINAGE SYSTEM AS DEPICTED ON THE APPROVED PLANS. SAID EASEMENT RIGHTS SHALL BE SPECIFICALLY DESCRIBED IN LEASE DOCUMENTS FOR THE PROJECT.

II. RESPONSIBLE PARTIES
THE OPERATOR OF THE SOLAR SYSTEM SHALL BE CONSIDERED THE RESPONSIBLE PARTY FOR THE OPERATION AND
MAINTENANCE OF THE STORMWATER MANAGEMENT SYSTEM. THE SYSTEM SHALL INCLUDE THE DRAINAGE INFRASTRUCTURE
AND ALL OF ITS COMPONENTS AS SHOWN ON THE APPROVED PLANS. THE SYSTEM SHALL ALSO INCLUDE THE DETENTION
FACILITIES AND THE OUTFALL AREAS OF THE DRAINAGE SYSTEM.

III. INSPECTION & MAINTENANCE SCHEDULE
THE FOLLOWING MAINTENANCE SCHEDULE SHALL BE FOLLOWED IN ORDER TO MAINTAIN THE EFFECTIVENESS OF THE STORMWATER MANAGEMENT SYSTEM.

STRUCTURE TYPE TWICE A YEAR REMOVE DEBRIS & ADD STONE RIP/RAP APRONS EVERY 10 YEARS SUBDRAINS TWICE A YEAR EVERY 4 YEARS REPLACE PEASTONE DETENTION BASINS MONTHLY (MAY-OCT) MONTHLY (MAY-OCT) MOW GRASS AREAS & REMOVE DEBRIS REMOVE SEDIMENT IF PRESENT **OUTFALL STRUCTURES:** EVERY 10 YEARS REMOVE DEBRIS & ADD STONE TWICE A YEAR

NOTE: THE DETENTION BASINS ON THIS PROJECT MAY GROW VEGETATION IN THE BOTTOM WHICH MAY INCLUDE SPECIES PART OF THE WETLAND PROTECTION ACT. THESE PLANTS SHALL NOT BE CONSTRUED AS HAVING PROTECTION UNDER THE ACT AND SHALL BE CONSIDERED OPPORTUNISTIC GROWTH PLANTS. ADDITIONALLY, THIS AREA SHALL NOT BE CONSIDERED A CONSTRUCTED WETLAND.

SEEDING OPERATION AND MAINTENANCE PLAN

I. RESPONSIBLE PARTIES

THE OPERATOR OF THE SOLAR SYSTEM SHALL BE CONSIDERED THE RESPONSIBLE PARTY FOR THE OPERATION AND MAINTENANCE OF THE GRASS & VEGETATION. THE VEGETATION SHALL INCLUDE ALL OF ITS AREAS AS SHOWN ON THE APPROVED PLANS. THE SYSTEM SHALL ALSO INCLUDE THE GRASSED AREAS AROUND THE PANELS AND DRAINAGE

II. INSPECTION & MAINTENANCE SCHEDULE
THE FOLLOWING MAINTENANCE SCHEDULE SHALL BE FOLLOWED IN ORDER TO MAINTAIN THE VEGETATED AREAS
ACTIVITY MAINTENANCE TASK

GRASS CUTTING MONTHLY GRASS HEIGHT TO BE ALLOWED TO GROW TO A HEIGHT OF NO MORE THAN 18 INCHES AND BE CUT TO A HEIGHT OF 4 TO 6 INCHES.

80 TO 100 POUNDS PER ACRE

III. APPROPIATE SEED MIX AND APPLICATION RATES

THE FOLLOWING SEED SCHEDULE SHALL BE FOLLOWED IN ORDER TO PROPERLY MAINTAIN VEGETATED AREAS

SEED TYPE (NATIVE SEED REQUIRED) APPLICATION RATE % OF MIX

WLDFLOWER SEED MIX 5 TO 10 POUNDS PER ACRE 50%


WHITE CLOVER SEED MIX 3 TO 5 POUNDS PER ACRE 10%

IV. HERBICIDES & PESTICIDES
THERE WILL NO HERBICIDES OR PESTICIDES USED ON THIS PROJECT.

KENTUCKY BLUEGRASS

2 11/15/21 GRADING REVISIONS CMA
1 10/19/21 PEER-REVIEW COMMENT CMA
NO. DATE REVISIONS BY

40%



|HANNIGAN |ENGINEERING, INC.

CIVIL ENGINEERS & LAND SURVEYORS

8 MONUMENT SQUARE (978) 534-1234 (T) LEOMINSTER, MASSACHUSETTS 01453 (978) 534-6060 (F)

CONSTRUCTION DETAILS
LEICESTER, MASSACHUSETTS

WWW.HANNIGANENGINEERING.COM

PREPARED FOR:

ZP BATTERY DEVCO, LLC

BRENDAN GOVE

10 E WORCESTER STREET SUITE 3A WORCESTER, MASSACHUSETTS 01604

IEL:

CALC: CMA	DRWN: CMA	SCALE: NA	
CHKD: WDH	APPD: WDH	DATE: SEP 21, 2021	
SRV: JEF	FB: 71–22	JOB NO: 3010	
TAB: (5-6) DET	SHEET 6 OF 6	PLAN N0:C-17-38	

APPLICANT:

ZP BATTERY DEVCO, LLC

BRENDON GOVE

10 E. WORCESTER STREET, SUIT 3A

WORCESTER, MASSACHUSETTS 01604

OWNER:

WR ENTERPRISES, LLC

1323 MAIN STREET

LEICESTER, MASSACHUSETTS 01524