## Tauper Land Surveying, Inc.

## **HYDRAULIC / HYDROLOGIC CALCULATIONS**

# Site Plan Stafford Street Leicester Massachusetts

Prepared For: Schold Development, LLC

Prepared By:

SUMMIT ENGINEERING & SURVEY, INC 710 MAIN STREET OXFORD, MASSACHUSETTS

April 5, 2022

#### **TABLE OF CONTENTS**

Cover Page

**Table of Contents** 

Drainage Summary

Stormwater Management Calculations
Standard #2 Peak Discharge Rates
Standard #3 Loss of Annual Recharge
Standard #4 80% TSS Removal
Standard #9 Operation & Maintenance Plan

#### Appendices

Pre-Development Diagram
Post- Development Diagram
Pre-Development Watershed Subcatchments
Post-Development Watershed Subcatchments
Soil Maps
Flood Map

## **DRAINAGE SUMMARY**

Summit Engineering & Survey, Inc. is pleased to provide the following Hydraulic / Hydrologic analysis for the proposed site plan for Schold Development. The proposed project is located on Stafford Street in Leicester, Massachusetts. The existing site consists of an undeveloped parcel, much of it wooded with mature woodland. The hydrologic conditions were analyzed using TR-55 and HydroCAD® for the 2, 10 and 100 year storm events utilizing Technical Paper 40, 24 hour Rainfall events.

Project site consists of theconstruting a warehouse off ice building with parking area and access onto Stafford Street, installation of proposed septic and well and grading the site so all runoff generated from the proposed development can be collected and treated and mitigated before discharing it toward the existing wetlands located on the site. The project as designed conforms to the Massachusetts DEP Stormwater Management Policy.

EXISTING CONDITIONS: The project is located on Stafford Street near the intersection of Auburn Street. The parcel is 8.7 acres in size. The site wooded and has not been disturbed. There is an existing wetland that running parallel with Stafford Street.

The topography of the site slopes toward the back of the parcel, which is toward existing wetlands.

For the purpose of the analysis of the effect on the parcel toward the existing wetlands, the site was analyzed as one watershed. In the Pre-Development Condition, Subcatchment 1 represents the tributary area of the property that flows to the back of the parcel and the existing wetlands.

According to the online USGS soil survey, the analyzed area consists of soils with "C" hydrologic ratings. Per the soil map the soil on site are Paxton. The cover consists of predominantly woodland area.

#### PROPOSED CONDITIONS:

The proposed condition of the site will consists of a woodland area and the proposed development will be adjacent to the Street. The proposed drainage system will consist of catch basins to manhole design the is directed into an underground basin. The site will also use proposed stormceptors to help clean the runoff before it enters the underground basin. In order to analyze the surface water flows, the site was divided into multiple Subcatchents, Ponds and a Reaches

In summary, the peak rates of runoff were compared under pre-development and post-development conditions for analysis of the 2 year, 10 year, 25 year and 100 year storm events. The following is a **Peak Discharge Summary Table**:

**Design Point Analysis:** 

<u>Tauper Land Surveying, Inc.</u> 710 Main Street North Oxford MA 01537 (P) 508-987-8713 (F) 508-987-8714

			Des	ign Event	
Wa	tershed	2 Year	10 Year	25 Year	100 Year
Pre-Development	IP#1E	0.20	1.18	1.61	3.08
Post Development	IP#1P	0.20	0.89	1.17	2.83
Post Dev					

#### **DEP Stormwater Management Standards:**

Standard #1: The proposed changes will not cause erosion in adjacent water of the Commonwealth, as BMP measures are proposed in accordance with the design requirements of the Stormwater Management handbook. The Erosion & Sedimentation Control Plan provides for the installation of siltation barriers, temporary basins, temporary construction entrances and outlines intermediary measures to control runoff during construction and after construction.

Standard #2: The proposed development peak discharge rates for the total off-site flow are less than or equal to pre-development discharge rates for the 2 year, 10 year, and 100 year storm events for the design points analyzed. Attached calculations show how the site mitigates the increased flow rates due to surface changes from the site development.

Standard #3: The proposed project does not propose any impervious area at this time. The proposed future site will address this Standard as required by Stormwater Management. The existing basin will continue to address this Standard as it was designed to infiltrate runoff from the Tractor Supply Site after pre-treatment. The existing basin will be monitored throughout the construction to ensure that the Infiltration depths are designed to drain in under 72 hours as required by the Policy.

Standard #4: Over 80% TSS shall occur based on the BMP measurements provided. The treatment train varies for each section. TSS worksheets are provided in the report for each treatment train in the site.

Standard #5: The proposed development will not generate higher potential pollutant loads and therefore will not require additional BMP practices.

Standard #6: The proposed project is not near a critical area.

Standard #7: The proposed project is not a redevelopment project.

Standard #8: Erosion and sediment control measures are proposed as part of the proposed project.

Standard #9: An Operation & Maintenance plan is provided within this document

Standard #10: This project does not propose any illicit discharges.

## STORMWATER MANAGEMENT CHECKLIST



Bureau of Resource Protection - Wetlands Program

## **Checklist for Stormwater Report**

## B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.


Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

## Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Longterm Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature



52/100la 4/7/22

#### Checklist

Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?

New development

Redevelopment

Mix of New Development and Redevelopment



Bureau of Resource Protection - Wetlands Program

## **Checklist for Stormwater Report**

## Checklist (continued)

LID Measures: Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project: No disturbance to any Wetland Resource Areas ☐ Site Design Practices (e.g. clustered development, reduced frontage setbacks) ☐ Reduced Impervious Area (Redevelopment Only) ☐ Minimizing disturbance to existing trees and shrubs □ LID Site Design Credit Requested: Credit 1 Credit 2 Credit 3 Use of "country drainage" versus curb and gutter conveyance and pipe ☐ Bioretention Cells (includes Rain Gardens) ☐ Constructed Stormwater Wetlands (includes Gravel Wetlands designs) Treebox Filter Water Quality Swale Grass Channel ☐ Green Roof Other (describe):

### Standard 1: No New Untreated Discharges

- No new untreated discharges
- Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Bureau of Resource Protection - Wetlands Program

## **Checklist for Stormwater Report**

Checklist (continued) Standard 2: Peak Rate Attenuation ☐ Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding. Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm. ☐ Calculations provided to show that post-development peak discharge rates do not exceed predevelopment rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24hour storm. Standard 3: Recharge Soil Analysis provided. Required Recharge Volume calculation provided. Required Recharge volume reduced through use of the LID site Design Credits. Sizing the infiltration, BMPs is based on the following method: Check the method used. Static
 St ☐ Simple Dynamic Dynamic Field<sup>1</sup> Runoff from all impervious areas at the site discharging to the infiltration BMP. Runoff from all impervious areas at the site is not discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume. Recharge BMPs have been sized to infiltrate the Required Recharge Volume. Recharge BMPs have been sized to infiltrate the Required Recharge Volume only to the maximum extent practicable for the following reason:

□ Calculations showing that the infiltration BMPs will drain in 72 hours are provided.

☐ Site is comprised solely of C and D soils and/or bedrock at the land surface

Project is otherwise subject to Stormwater Management Standards only to the maximum extent

M.G.L. c. 21E sites pursuant to 310 CMR 40.0000

Solid Waste Landfill pursuant to 310 CMR 19.000

practicable.

Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

<sup>&</sup>lt;sup>1</sup> 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Bureau of Resource Protection - Wetlands Program

## Checklist for Stormwater Report

#### Checklist (continued)

#### Standard 3: Recharge (continued)

$\boxtimes$	The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10- /ear 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
	analysis is provided.

 Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

#### Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
- Provisions for storing materials and waste products inside or under cover;
- Vehicle washing controls;
- Requirements for routine inspections and maintenance of stormwater BMPs;
- Spill prevention and response plans;
- Provisions for maintenance of lawns, gardens, and other landscaped areas;
- Requirements for storage and use of fertilizers, herbicides, and pesticides;
- Pet waste management provisions:
- Provisions for operation and management of septic systems;
- Provisions for solid waste management;
- Snow disposal and plowing plans relative to Wetland Resource Areas;
- Winter Road Salt and/or Sand Use and Storage restrictions;
- Street sweeping schedules;
- Provisions for prevention of illicit discharges to the stormwater management system;
- Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
- Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
- List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.

	s and
$\boxtimes$	A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
	Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
	is within the Zone II or Interim Wellhead Protection Area
	is near or to other critical areas
	is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
	involves runoff from land uses with higher potential pollutant loads.
	The Required Water Quality Volume is reduced through use of the LID site Design Credits.

Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if

applicable, the 44% TSS removal pretreatment requirement, are provided.



Bureau of Resource Protection - Wetlands Program

## **Checklist for Stormwater Report**

Checklist (continued) Standard 4: Water Quality (continued) The BMP is sized (and calculations provided) based on: ∑ The ½" or 1" Water Quality Volume or ☐ The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume. The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs. A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided. Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs) ☐ The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report. ☐ The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted *prior* to the discharge of stormwater to the post-construction stormwater BMPs. ☐ The NPDES Multi-Sector General Permit does *not* cover the land use. LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan. All exposure has been eliminated. All exposure has *not* been eliminated and all BMPs selected are on MassDEP LUHPPL list. ☐ The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

#### Standard 6: Critical Areas

The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.

Critical areas and BMPs are identified in the Stormwater Report.



Bureau of Resource Protection - Wetlands Program

## **Checklist for Stormwater Report**

## Checklist (continued)

Sta	andard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum tent practicable								
	The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:								
	☐ Limited Project								
	<ul> <li>☐ Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.</li> <li>☐ Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area</li> <li>☐ Marina and/or hostvard provided the bull pointing a series of the family houses.</li> </ul>								
	Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff								
	☐ Bike Path and/or Foot Path								
	Redevelopment Project								
	Redevelopment portion of mix of new and redevelopment.								
	Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.  The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist foun in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.								
Stan	ndard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control								

### S

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.
- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.




## Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program

## **Checklist for Stormwater Report**

	Checklist (continued)								
<b>S</b>	tandard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control								
	The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has <i>not</i> been included in the Stormwater Report but will be submitted <i>before</i> land disturbance begins.								
	The project is <i>not</i> covered by a NPDES Construction General Permit.								
	The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.								
	The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.								
St	tandard 9: Operation and Maintenance Plan								
$\boxtimes$	The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:								
	Name of the stormwater management system owners;								
	☑ Party responsible for operation and maintenance;								
	Schedule for implementation of routine and non-routine maintenance tasks;								
	☑ Plan showing the location of all stormwater BMPs maintenance access areas;								
	☐ Description and delineation of public safety features;								
	○ Operation and Maintenance Log Form.								
	The responsible party is <b>not</b> the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:								
	<ul> <li>A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;</li> </ul>								
	A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.								
Sta	andard 10: Prohibition of Illicit Discharges								
$\boxtimes$	The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;								
$\boxtimes$	An Illicit Discharge Compliance Statement is attached;								
	NO Illicit Discharge Compliance Statement is attached but will be submitted <i>prior to</i> the discharge of any stormwater to post-construction BMPs.								

## **STANDARD #2- PEAK DISCHARGE RATES**



Printed 4/6/2022 Page 2

#### Area Listing (all nodes)

 Area (acres)	CN	Description (subcatchment-numbers)
0.234	61	>75% Grass cover, Good, HSG B (1P, 2P, 3S)
0.200	98	Paved parking, HSG B (2P, 3S)
0.262	98	Paved parking, HSG C (1P)
1.905	55	Woods, Good, HSG B (1S, 3S)
0.184	58	Woods/grass comb., Good, HSG B (1S)
2.786	63	TOTAL AREA

Printed 4/6/2022 Page 3

### Soil Listing (all nodes)

-	Area (acres)	Soil Group	Subcatchment Numbers
	0.000	HSG A	
	2.524	HSG B	1P, 1S, 2P, 3S
	0.262	HSG C	1P
	0.000	HSG D	
	0.000	Other	
	2.786		<b>TOTAL AREA</b>

Printed 4/6/2022 Page 4

## Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.234	0.000	0.000	0.000	0.234	>75% Grass cover, Good	1P,
0.000	0.200	0.262	0.000	0.000	0.462	Paved parking	2P, 3S 1P,
0.000 0.000 <b>0.000</b>	1.905 0.184 <b>2.524</b>	0.000 0.000 <b>0.262</b>	0.000 0.000 <b>0.000</b>	0.000 0.000 <b>0.000</b>	1.905 0.184 <b>2.786</b>	Woods, Good Woods/grass comb., Good TOTAL AREA	2P, 3S 1S, 3S 1S

Type III 24-hr 2YR Rainfall=3.40"

Prepared by {enter your company name here}
HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 5

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1P: 1P

Runoff Area=13,258 sf 85.99% Impervious Runoff Depth>2.49"

Tc=6.0 min CN=93 Runoff=0.89 cfs 0.063 af

Subcatchment 1S: DA 1

Runoff Area=60,669 sf 0.00% Impervious Runoff Depth>0.27"

Tc=6.0 min CN=55 Runoff=0.20 cfs 0.031 af

Subcatchment 2P: 2P

Runoff Area=12,229 sf 54.79% Impervious Runoff Depth>1.51"

Tc=6.0 min CN=81 Runoff=0.52 cfs 0.035 af

Subcatchment 3S: 3P

Runoff Area=35,182 sf 5.76% Impervious Runoff Depth>0.36"

Tc=6.0 min CN=58 Runoff=0,21 cfs 0.024 af

Reach IP-E1: Wetlands

Inflow=0.20 cfs 0.031 af

Outflow=0.20 cfs 0.031 af

Reach IP-P1: Wetlands

Inflow=0.21 cfs 0.024 af

Outflow=0.21 cfs 0.024 af

Pond PND 1: PND 1

Peak Elev=782.84' Storage=2,286 cf Inflow=1.41 cfs 0.099 af

Discarded=0.07 cfs 0.061 af Primary=0.00 cfs 0.000 af Outflow=0.07 cfs 0.061 af

Total Runoff Area = 2.786 ac Runoff Volume = 0.154 af Average Runoff Depth = 0.66" 83.41% Pervious = 2.323 ac 16.59% Impervious = 0.462 ac

Printed 4/6/2022 Page 6

#### Summary for Subcatchment 1P: 1P

Runoff


0.89 cfs @ 12.09 hrs, Volume=

0.063 af, Depth> 2.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 2YR Rainfall=3.40"

_	А	rea (sf)	CN	Description			
		11,400		Paved park			
_		1,858	61	>75% Gras	s cover, Go	ood, HSG B	
		13,258		Weighted A			
		1,858		14.01% Per			
		11,400		85.99% Imp			
	Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description	
	6.0					Direct Entry, TRAVEL PATH	

#### Subcatchment 1P: 1P



Page 7

#### Summary for Subcatchment 1S: DA 1


Runoff = 0.20 cfs @ 12.29 hrs, Volume=

0.031 af, Depth> 0.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 2YR Rainfall=3.40"

A	rea (sf)	CN	Description							
	52,634	55	Woods, Go	Woods, Good, HSG B						
	8,035	58	Woods/gras	Noods/grass comb., Good, HSG B						
	60,669 60,669	55	Weighted A 100.00% Pe	verage						
Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description					
6.0					Direct Entry TRAVEL PATH					

#### Subcatchment 1S: DA 1



Printed 4/6/2022 Page 8

### Summary for Subcatchment 2P: 2P


Runoff = 0.52 cfs @ 12.09 hrs, Volume=

0.035 af, Depth> 1.51"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 2YR Rainfall=3.40"

Area	a (sf) CN	Description	Description						
6	,700 98	Paved park	aved parking, HSG B						
5	,529 61		>75% Grass cover, Good, HSG B						
5	2,229 81 5,529 5,700	Weighted A 45.21% Per	Weighted Average 45.21% Pervious Area 54.79% Impervious Area						
(min)	ength Slo (feet) (ft/		Capacity (cfs)	Description					
6.0				Direct Entry, TRAVEL PATH					

#### Subcatchment 2P: 2P



Printed 4/6/2022

Page 9

### Summary for Subcatchment 3S: 3P

Runoff


0.21 cfs @ 12.15 hrs, Volume=

0.024 af, Depth> 0.36"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 2YR Rainfall=3.40"

A	rea (sf)	CN	Description							
	30,354	55	Woods, Good, HSG B							
	2,027	98	Paved parking, HSG B							
	2,801				ood, HSG B					
35,182 58 Weighted Average 33,155 94.24% Pervious Area 2,027 5.76% Impervious Area				vious Area						
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description					
6.0					Direct Entry TRAVEL PAT	п				

#### Subcatchment 3S: 3P



Type III 24-hr 2YR Rainfall=3.40"

Prepared by {enter your company name here}
HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022 Page 10

## Summary for Reach IP-E1: Wetlands


Inflow Area = 1.393 ac, 0.00% Impervious, Inflow Depth > 0.27" for 2YR event

Inflow = 0.20 cfs @ 12.29 hrs, Volume= 0.031 af

Outflow = 0.20 cfs @ 12.29 hrs, Volume= 0.031 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

#### Reach IP-E1: Wetlands



Type III 24-hr 2YR Rainfall=3.40" Printed 4/6/2022

Prepared by {enter your company name here} HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Page 11

#### Summary for Reach IP-P1: Wetlands


Inflow Area = 1.393 ac, 33.18% Impervious, Inflow Depth > 0.21" for 2YR event

Inflow 0.024 af

0.21 cfs @ 12.15 hrs, Volume= 0.21 cfs @ 12.15 hrs, Volume= Outflow 0.024 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

#### Reach IP-P1: Wetlands



Type III 24-hr 2YR Rainfall=3.40"

Prepared by {enter your company name here} HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022 Page 12

### Summary for Pond PND 1: PND 1

Inflow Area = 0.585 ac, 71.02% Impervious, Inflow Depth > 2.02" for 2YR event Inflow

1.41 cfs @ 12.09 hrs, Volume= 0.099 af

Outflow = 0.07 cfs @ 11.30 hrs, Volume= 0.061 af, Atten= 95%, Lag= 0.0 min

0.07 cfs @ 11.30 hrs, Volume= Discarded = 0.061 af Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 782.84' @ 14.73 hrs Surf.Area= 3,036 sf Storage= 2,286 cf

Plug-Flow detention time= 189.2 min calculated for 0.061 af (62% of inflow) Center-of-Mass det. time= 113.4 min ( 887.8 - 774.4 )

Volume	Invert	Avail.Storage	Storage Description
#1	782.00'	2,306 cf	
#2	782.00'	4,862 cf	Cultec R-330XLHD x 90 Inside #1  Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf  Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap  Row Length Adjustment= +1.50' x 7.45 sf x 15 rows

7,167 cf Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
782.00	3,036	0	0
785.50	3,036	10,626	10,626

Device	Routing	Invert	Outlet Devices	
#1	Discarded	782.00'	1.020 in/hr Exfiltration over Surface area	_
#2	Primary		6.0" Vert. Orifice/Grate C= 0.600	
#3	Primary		8.0" Vert. Orifice/Grate C= 0.600	

Discarded OutFlow Max=0.07 cfs @ 11.30 hrs HW=782.04' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.07 cfs)


Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=782.00' (Free Discharge)

-2=Orifice/Grate (Controls 0.00 cfs) -3=Orifice/Grate (Controls 0.00 cfs)

Printed 4/6/2022

Page 13

Pond PND 1: PND 1



Type III 24-hr 10YR Rainfall=4.90"

Prepared by {enter your company name here}
HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 14

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1P: 1P

Runoff Area=13,258 sf 85.99% Impervious Runoff Depth>3.87"

Tc=6.0 min CN=93 Runoff=1.35 cfs 0.098 af

Subcatchment 1S: DA 1

Runoff Area=60,669 sf 0.00% Impervious Runoff Depth>0.83"

Tc=6.0 min CN=55 Runoff=1.18 cfs 0.096 af

Subcatchment 2P: 2P

Runoff Area=12,229 sf 54.79% Impervious Runoff Depth>2.71"

Tc=6.0 min CN=81 Runoff=0.93 cfs 0.063 af

Subcatchment 3S: 3P

Runoff Area=35,182 sf 5.76% Impervious Runoff Depth>1.00"

Tc=6.0 min CN=58 Runoff=0.89 cfs 0.067 af

Reach IP-E1: Wetlands

Inflow=1.18 cfs 0.096 af

Outflow=1.18 cfs 0.096 af

Reach IP-P1: Wetlands

Inflow=0.89 cfs 0.112 af

Outflow=0.89 cfs 0.112 af

Pond PND 1: PND 1

Peak Elev=783.19' Storage=3,191 cf Inflow=2.28 cfs 0.162 af

Discarded=0.07 cfs 0.068 af Primary=0.40 cfs 0.045 af Outflow=0.47 cfs 0.113 af

Total Runoff Area = 2.786 ac Runoff Volume = 0.325 af Average Runoff Depth = 1.40" 83.41% Pervious = 2.323 ac 16.59% Impervious = 0.462 ac

Printed 4/6/2022

Page 15

### Summary for Subcatchment 1P: 1P

Runoff


1.35 cfs @ 12.09 hrs, Volume=

0.098 af, Depth> 3.87"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 10YR Rainfall=4.90"

	Area (sf)	CN	Description				
	11,400 98 Paved parking, HSG C						
1,858 61 >75% Grass cover, Good, HSG B							
	13,258	93	Weighted A	verage			
	1,858		14.01% Per				
	11,400		85.99% Impervious Area				
To (min		Slope (ft/ft)	,	Capacity (cfs)	Description		
6.0	)				Direct Entry, TRAVEL PATH		

#### Subcatchment 1P: 1P



Printed 4/6/2022

Page 16

#### Summary for Subcatchment 1S: DA 1


Runoff = 1.18 cfs @ 12.11 hrs, Volume=

0.096 af, Depth> 0.83"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 10YR Rainfall=4.90"

	A	rea (sf)	CN	Description			
		52,634	55	Woods, Go	od, HSG B		
-		8,035				Good, HSG B	
		60,669 60,669		Weighted A 100.00% Pe	verage		
_	Tc (min)	Length (feet)	Slope (ft/ft		Capacity (cfs)	Description	
	6.0					Direct Entry, TRAVEL PATH	

#### Subcatchment 1S: DA 1



Printed 4/6/2022

Page 17

### Summary for Subcatchment 2P: 2P

Runoff

=


0.93 cfs @ 12.09 hrs, Volume=

0.063 af, Depth> 2.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 10YR Rainfall=4.90"

	Area (sf)	CN	Description			
	6,700	98	Paved park	ing, HSG E		
	5,529				ood, HSG B	
	12,229 5,529 6,700	81	Weighted A 45.21% Per 54.79% Imp	verage rvious Area		
(mi	c Length n) (feet)	Slope (ft/ft		Capacity (cfs)	Description	
6	.0				Direct Entry, TRAVEL PATH	

#### Subcatchment 2P: 2P



Printed 4/6/2022

#### Page 18

#### Summary for Subcatchment 3S: 3P

Runoff


0.89 cfs @ 12.11 hrs, Volume=

0.067 af, Depth> 1.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 10YR Rainfall=4.90"

	Area (sf) CN Description							
	30,354 55 Woods, Good, HSG B							
	2,027 98 Paved parking, HSG B 2,801 61 >75% Grass cover, God							
-								
	35,182 58 Weighted Average 33,155 94.24% Pervious Area 2,027 5.76% Impervious Area							
-	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description		
	6.0					Direct Entry	TRAVEL DATH	

#### Subcatchment 3S: 3P



Printed 4/6/2022

Page 19

#### Summary for Reach IP-E1: Wetlands

Inflow Area =

1.393 ac, 0.00% Impervious, Inflow Depth > 0.83" for 10YR event

Inflow

1.18 cfs @ 12.11 hrs, Volume=

0.096 af


Outflow

1.18 cfs @ 12.11 hrs, Volume=

0.096 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

#### Reach IP-E1: Wetlands



Type III 24-hr 10YR Rainfall=4.90"

Prepared by {enter your company name here} HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 20

### Summary for Reach IP-P1: Wetlands


1.393 ac, 33.18% Impervious, Inflow Depth > 0.96" for 10YR event Inflow Area =

Inflow 0.112 af

0.89 cfs @ 12.11 hrs, Volume= 0.89 cfs @ 12.11 hrs, Volume= Outflow 0.112 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

#### Reach IP-P1: Wetlands



Type III 24-hr 10YR Rainfall=4.90"

Prepared by {enter your company name here} HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 21

### Summary for Pond PND 1: PND 1

0.045 af

Inflow Area = 0.585 ac, 71.02% Impervious, Inflow Depth > 3.31" for 10YR event Inflow 2.28 cfs @ 12.09 hrs, Volume= 0.162 af Outflow = 0.47 cfs @ 12.52 hrs, Volume= 0.113 af, Atten= 79%, Lag= 26.0 min Discarded = 0.07 cfs @ 10.30 hrs, Volume= 0.068 af Primary =

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 783.19' @ 12.52 hrs Surf.Area= 3,036 sf Storage= 3,191 cf

0.40 cfs @ 12.52 hrs, Volume=

Plug-Flow detention time= 138.8 min calculated for 0.113 af (70% of inflow) Center-of-Mass det. time= 71.2 min (836.3 - 765.1)

Volume	Invert	Avail.Storage	Storage Description
#1	782.00'	2,306 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#2	782.00'	4,862 cf	10,626 cf Overall - 4,862 cf Embedded = 5,764 cf x 40.0% Voids <b>Cultec R-330XLHD</b> x 90 Inside #1
			Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap
		7.407.6	Row Length Adjustment= +1.50' x 7.45 sf x 15 rows

7,167 cf Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
782.00	3,036	0	0
785.50	3,036	10,626	10,626

Device	Routing	Invert	Outlet Devices		
#1 #2 #3	Discarded Primary Primary	782.85'	1.020 in/hr Exfiltration o 6.0" Vert. Orifice/Grate 8.0" Vert. Orifice/Grate	C= 0.600	

Piscarded OutFlow Max=0.07 cfs @ 10.30 hrs HW=782.04' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.07 cfs)


Primary OutFlow Max=0.39 cfs @ 12.52 hrs HW=783.19' (Free Discharge)

-2=Orifice/Grate (Orifice Controls 0.28 cfs @ 1.97 fps) -3=Orifice/Grate (Orifice Controls 0.12 cfs @ 1.47 fps)

Printed 4/6/2022

Software Solutions LLC Page 22





Type III 24-hr 25YR Rainfall=5.40"

Prepared by {enter your company name here}
HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 23

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1P: 1P Runoff Area=13,258 sf 85.99% Impervious Runoff Depth>4.33"

Tc=6.0 min CN=93 Runoff=1.50 cfs 0.110 af

Subcatchment 1S: DA 1 Runoff Area=60,669 sf 0.00% Impervious Runoff Depth>1.06"

Tc=6.0 min CN=55 Runoff=1.61 cfs 0.123 af

Subcatchment 2P: 2P Runoff Area=12,229 sf 54.79% Impervious Runoff Depth>3.13"

Tc=6.0 min CN=81 Runoff=1.07 cfs 0.073 af

Subcatchment 3S: 3P Runoff Area=35,182 sf 5.76% Impervious Runoff Depth>1.26"

Tc=6.0 min CN=58 Runoff=1.17 cfs 0.085 af

Reach IP-E1: Wetlands Inflow=1.61 cfs 0.123 af

Outflow=1.61 cfs 0.123 af

Reach IP-P1: Wetlands Inflow=1.17 cfs 0.147 af

Outflow=1.17 cfs 0.147 af

Pond PND 1: PND 1 Peak Elev=783.28' Storage=3,419 cf Inflow=2.57 cfs 0.183 af

Discarded=0.07 cfs 0.070 af Primary=0.64 cfs 0.063 af Outflow=0.71 cfs 0.133 af

Total Runoff Area = 2.786 ac Runoff Volume = 0.391 af Average Runoff Depth = 1.69" 83.41% Pervious = 2.323 ac 16.59% Impervious = 0.462 ac

Printed 4/6/2022

Page 24

### Summary for Subcatchment 1P: 1P

Runoff


1.50 cfs @ 12.09 hrs, Volume=

0.110 af, Depth> 4.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 25YR Rainfall=5.40"

A	rea (sf)	CN [	Description				
	11,400 1,858	98 F	Paved parking, HSG C >75% Grass cover, Good, HSG B				
	13,258 1,858 11,400	93 \	Weighted Average 14.01% Pervious Area 85.99% Impervious Area				
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description		
6.0					Direct Entry TRAVEL BATH		

### Subcatchment 1P: 1P



Printed 4/6/2022

Page 25

### Summary for Subcatchment 1S: DA 1


Runoff = 1.61 cfs @ 12.11 hrs, Volume=

0.123 af, Depth> 1.06"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 25YR Rainfall=5.40"

	Area (sf)	CN	Description					
	52,634	55	Woods, Good, HSG B					
	8,035			/oods/grass comb., Good, HSG B				
	60,669 60,669		Weighted A 100.00% Po	verage				
T (mir	c Length n) (feet)	Slope (ft/ft		Capacity (cfs)	Description			
6.	0		- Marian		Direct Entry TRAVEL BATH			

### Subcatchment 1S: DA 1



Printed 4/6/2022

Page 26

### Summary for Subcatchment 2P: 2P


Runoff = 1.07 cfs @ 12.09 hrs, Volume=

0.073 af, Depth> 3.13"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 25YR Rainfall=5.40"

Are	a (sf)	CN	Description					
6	5,700	98	Paved park	ing, HSG E				
	5,529			75% Grass cover, Good, HSG B				
5	2,229 5,529 6,700	81	Weighted A 15.21% Per 54.79% Imp	verage vious Area				
Tc L (min)	ength (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
6.0					Direct Entry, TRAVEL PATH			

### Subcatchment 2P: 2P



Printed 4/6/2022

Page 27

### Summary for Subcatchment 3S: 3P


Runoff = 1.17 cfs @ 12.10 hrs, Volume=

0.085 af, Depth> 1.26"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 25YR Rainfall=5.40"

	A	rea (sf)	CN	Description	escription				
		30,354	55	Voods, Good, HSG B					
		2,027	98	Paved park	Paved parking, HSG B				
_		2,801				ood, HSG B			
		35,182 33,155 2,027		Weighted Average 94.24% Pervious Area 5.76% Impervious Area					
7. <u>-</u>	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
	6.0					Direct Entry, TRAVEL PATH			

### Subcatchment 3S: 3P



Printed 4/6/2022

Page 28

### Summary for Reach IP-E1: Wetlands


1.393 ac, 0.00% Impervious, Inflow Depth > 1.06" for 25YR event Inflow Area = Inflow

1.61 cfs @ 12.11 hrs, Volume= 0.123 af

Outflow 1.61 cfs @ 12.11 hrs, Volume= 0.123 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Reach IP-E1: Wetlands



Printed 4/6/2022

Page 29

### Summary for Reach IP-P1: Wetlands

Inflow Area =

1.393 ac, 33.18% Impervious, Inflow Depth > 1.27" for 25YR event

Inflow =

1.17 cfs @ 12.11 hrs, Volume=

0.147 af


Outflow

1.17 cfs @ 12.11 hrs, Volume=

0.147 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Reach IP-P1: Wetlands



Type III 24-hr 25YR Rainfall=5.40"

Prepared by {enter your company name here} HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 30

### Summary for Pond PND 1: PND 1

Inflow Area = 0.585 ac, 71.02% Impervious, Inflow Depth > 3.76" for 25YR event Inflow 2.57 cfs @ 12.09 hrs, Volume= 0.183 af Outflow = 0.71 cfs @ 12.45 hrs, Volume= 0.133 af, Atten= 72%, Lag= 21.5 min 0.07 cfs @ 9.95 hrs, Volume= 0.64 cfs @ 12.45 hrs, Volume= Discarded = 0.070 af Primary = 0.063 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 783.28' @ 12.45 hrs Surf.Area= 3,036 sf Storage= 3,419 cf

Plug-Flow detention time= 126.5 min calculated for 0.133 af (72% of inflow) Center-of-Mass det. time= 62.0 min (824.8 - 762.8)

Volume	Invert	Avail.Storage	Storage Description
#1	782.00'	2,306 cf	
#2	782.00'	4,862 cf	10,626 cf Overall - 4,862 cf Embedded = 5,764 cf x 40.0% Voids Cultec R-330XLHD x 90 Inside #1  Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf  Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap  Row Length Adjustment= +1.50' x 7.45 sf x 15 rows
-		7.407.6	1.00 X 7.45 SI X 15 10WS

7,167 cf Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
782.00	3,036	0	0
785.50	3,036	10,626	10.626

Device	Routing	Invert	Outlet Devices		
#1	Discarded	782.00'	1.020 in/hr Exfiltration of	ver Surface area	
#2	Primary	782.85	6.0" Vert. Orifice/Grate	C= 0.600	
#3	Primary	783.00	8.0" Vert. Orifice/Grate	C= 0.600	

Discarded OutFlow Max=0.07 cfs @ 9.95 hrs HW=782.04' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.07 cfs)

Primary OutFlow Max=0.64 cfs @ 12.45 hrs HW=783.28' (Free Discharge)


-2=Orifice/Grate (Orifice Controls 0.40 cfs @ 2.22 fps)

-3=Orifice/Grate (Orifice Controls 0.24 cfs @ 1.79 fps)

Printed 4/6/2022

Page 31

### Pond PND 1: PND 1



Type III 24-hr 100YR Rainfall=6.90"

Prepared by {enter your company name here}
HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 32

Time span=5.00-20.00 hrs, dt=0.05 hrs, 301 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1P: 1P Runoff Area=13,258 sf 85.99% Impervious Runoff Depth>5.72"

Tc=6.0 min CN=93 Runoff=1.95 cfs 0.145 af

Subcatchment 1S: DA 1 Runoff Area=60,669 sf 0.00% Impervious Runoff Depth>1.87"

Tc=6.0 min CN=55 Runoff=3.08 cfs 0.217 af

Subcatchment 2P: 2P Runoff Area=12,229 sf 54.79% Impervious Runoff Depth>4.43"

Tc=6.0 min CN=81 Runoff=1.50 cfs 0.104 af

Subcatchment 3S: 3P Runoff Area=35,182 sf 5.76% Impervious Runoff Depth>2.14"

Tc=6.0 min CN=58 Runoff=2.09 cfs 0.144 af

Reach IP-E1: Wetlands Inflow=3.08 cfs 0.217 af

Outflow=3.08 cfs 0.217 af

Reach IP-P1: Wetlands Inflow=2.83 cfs 0.264 af

Outflow=2.83 cfs 0.264 af

Pond PND 1: PND 1 Peak Elev=783.55' Storage=4,089 cf Inflow=3.45 cfs 0.249 af

Discarded=0.07 cfs 0.075 af Primary=1.40 cfs 0.120 af Outflow=1.47 cfs 0.195 af

Total Runoff Area = 2.786 ac Runoff Volume = 0.610 af Average Runoff Depth = 2.63" 83.41% Pervious = 2.323 ac 16.59% Impervious = 0.462 ac

Type III 24-hr 100YR Rainfall=6.90"

Prepared by {enter your company name here}
HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022 Page 33

### Summary for Subcatchment 1P: 1P

Runoff


1.95 cfs @ 12.09 hrs, Volume=

0.145 af, Depth> 5.72"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 100YR Rainfall=6.90"

	Α	rea (sf)	CN	Description				
		11,400 1,858	98 61	Paved parking, HSG C >75% Grass cover, Good, HSG B				
		13,258 1,858 11,400	93	Weighted A 14.01% Per 85.99% Imp	verage vious Area			
(n	Tc nin)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description		
	6.0			27.25		Direct Entry, TRAVEL PATH		

### Subcatchment 1P: 1P



Printed 4/6/2022

Page 34

### Summary for Subcatchment 1S: DA 1

Runoff


3.08 cfs @ 12.10 hrs, Volume=

0.217 af, Depth> 1.87"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 100YR Rainfall=6.90"

	rea (sf)	CN	Description					
	52,634	55	Woods, Good, HSG B					
	8,035			Voods/grass comb., Good, HSG B				
	60,669 60,669	55	Weighted A 100.00% Pe	verage				
Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description			
6.0					Direct Entry, TRAVEL PATH			

### Subcatchment 1S: DA 1



Printed 4/6/2022

Page 35

### Summary for Subcatchment 2P: 2P

Runoff

1.50 cfs @ 12.09 hrs, Volume=


0.104 af, Depth> 4.43"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 100YR Rainfall=6.90"

130	Are	ea (sf)	CN [	Description					
		6,700 5,529		Paved parking, HSG B >75% Grass cover, Good, HSG B					
	9	2,229 5,529 6,700	81 V	Veighted A 5.21% Per					
-	(min)	ength	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
	6.0					Direct Fotos	TDANEL DATE	//////////////////////////////////////	

### Direct Entry, TRAVEL PATH

### Subcatchment 2P: 2P



Type III 24-hr 100YR Rainfall=6.90"

Prepared by {enter your company name here} HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022 Page 36

### Summary for Subcatchment 3S: 3P


Runoff = 2.09 cfs @ 12.10 hrs, Volume=

0.144 af, Depth> 2.14"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type III 24-hr 100YR Rainfall=6.90"

Area	(sf) CN	Description	Description					
30,	354 55	Woods, Go	Woods, Good, HSG B					
2,	027 98		Paved parking, HSG B					
2,	801 61	>75% Gras	s cover, Go	ood, HSG B				
33,	182 58 155 027	Weighted A 94.24% Per 5.76% Impe	verage vious Area					
(min)(	ength Slope feet) (ft/ft	the second contract of the second	Capacity (cfs)	Description				
6.0				Direct Entry, TRAVEL PATH				

### Subcatchment 3S: 3P



Type III 24-hr 100YR Rainfall=6.90"

Prepared by {enter your company name here}

Printed 4/6/2022

Page 37

HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

### Summary for Reach IP-E1: Wetlands


1.393 ac, 0.00% Impervious, Inflow Depth > 1.87" for 100YR event Inflow Area =

Inflow 3.08 cfs @ 12.10 hrs, Volume= 0.217 af

Outflow 3.08 cfs @ 12.10 hrs, Volume= 0.217 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Reach IP-E1: Wetlands



Type III 24-hr 100YR Rainfall=6.90"

Prepared by {enter your company name here} HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 38

### Summary for Reach IP-P1: Wetlands


1.393 ac, 33.18% Impervious, Inflow Depth > 2.27" for 100YR event Inflow Area =

Inflow 0.264 af

2.83 cfs @ 12.15 hrs, Volume= 2.83 cfs @ 12.15 hrs, Volume= Outflow 0.264 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

### Reach IP-P1: Wetlands



Type III 24-hr 100YR Rainfall=6.90"

Prepared by {enter your company name here}
HydroCAD® 10.00-26 s/n 09589 © 2020 HydroCAD Software Solutions LLC

Printed 4/6/2022

Page 39

### Summary for Pond PND 1: PND 1

Inflow Area = 0.585 ac, 71.02% Impervious, Inflow Depth > 5.10" for 100YR event

1.47 cfs @ 12.29 hrs, Volume= 0.249 af

1.47 cfs @ 12.29 hrs, Volume= 0.195 af, Atten= 57%, Lag= 12.4 min

1.47 cfs @ 9.10 hrs, Volume= 0.075 af

1.40 cfs @ 12.29 hrs, Volume= 0.120 af

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Peak Elev= 783.55' @ 12.30 hrs Surf.Area= 3,036 sf Storage= 4,089 cf

Plug-Flow detention time= 104.0 min calculated for 0.195 af (78% of inflow) Center-of-Mass det. time= 47.5 min ( 804.9 - 757.3 )

Volume	Invert	Avail.Storage	Storage Description
#1	782.00'	2,306 cf	The stage Dutte (1 Homatio) Liotod Bolow (1 Codic)
<b>40</b>	700 001	4.000 4	10,626 cf Overall - 4,862 cf Embedded = 5,764 cf x 40.0% Voids
#2	782.00'	4,862 cf	
			Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf
			Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap
			Row Length Adjustment= +1.50' x 7.45 sf x 15 rows

7,167 cf Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
782.00	3,036	0	0
785.50	3,036	10,626	10,626

Device	Routing	Invert	Outlet Devices		
#1	Discarded	782.00'	1.020 in/hr Exfiltration of	over Surface area	
#2	Primary	782.85'	6.0" Vert. Orifice/Grate	C= 0.600	
#3	Primary	783.00'	8.0" Vert. Orifice/Grate	C= 0.600	

Discarded OutFlow Max=0.07 cfs @ 9.10 hrs HW=782.04' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.07 cfs)


Primary OutFlow Max=1.40 cfs @ 12.29 hrs HW=783.55' (Free Discharge)

**2=Orifice/Grate** (Orifice Controls 0.63 cfs @ 3.21 fps) **3=Orifice/Grate** (Orifice Controls 0.77 cfs @ 2.51 fps)

Printed 4/6/2022

Page 40

### Pond PND 1: PND 1



### STANDARD #3 -LOSS OF ANNUAL RECHARGE

The site is predominately un-developed. Temporary Basin 1& 2 are constructed for pretreatment prior to the existing wetland located in the west corner of the parcel. Soils were found to be Class C permeability.

The table below shows the required and provided recharge volumes for the project. As shown, the proposed condition exceeds the minimum requirement for the additional impervious areas.

**Recharge Volume Summary** 

		8	- arritially	NAME OF TAXABLE PARTY.
Soil Type	Recharge Factor (in. runoff)	Existing Impervious Area (sf)	Additional Impervious Area (sf)	Min. Req. Recharge Volume (cf)
Α	0.60	0	0	0
В	0.35	0	0	0
С	0.25	0	28,064	585
D	0.10	0	0	0
Total Re	quired			0

Standard #3 Only Applies to Additional Impervious

Provided Recharg	e Volume (cf)
(Pond#1)	1,954
	0
	0
Total Provided	1,954

### **Rechage Volume Calculation:**

 $Rv = F \times I$ 

Rv = Required Rechareg Volume

F = Recharge Factor

I = Total Impervious Area

 $Rv = (0.25")/(1'/12") \times 28,064 \text{ s.f.} = 585 \text{ cf (Required)}$ 

Provided Infiltration is 1,954 cf taken from Stage Storage Worksheet

### **Drawdown Calculation:**

$$Time_{drawdown} = \frac{Rv}{(K)(Bottom\ Area)}$$

Where:

Rv = Storage Volume (585 c.f.)

K = Saturated Hydraulic Conductivity For "Static" and "Simple Dynamic" Methods, use Rawls Rate (see Table 2.3.3). For "Dynamic Field" Method, use 50% of the in-situ saturated hydraulic conductivity. (1.02 in/hour)

Bottom Area = Bottom Area of Recharge Structure (2,442 s.f.)

Time = 585 c.f./ (1.02 in/hour)(1 inch/ 12 foot)(2,442 1/ 12 s.f.) = 1 hours

	STA	AGE-STC	RAGE W	ORKSHEET		
	DATE:	4/5/2022		CLIENT:		
PROJE	CT NUMBER:		C	ALCULATED BY:	PML	
BAS	IN NUMBER:	1		CHECKED BY:		
	LOCATION:	BASIN 1				
		<b>AVERAGE</b>	VERTICAL	VOLUME	VOLUME	
ELEVATION	AREA	AREA	INTERVAL	INCREMENTAL	CUMULATIVE	
(FEET)	(FT <sup>2</sup> )	(FT <sup>2</sup> )	(FT)	(FT <sup>3</sup> )	(FT <sup>3</sup> )	
102.0	2442				0	
102.8	2442	2442	1	1954	1954	

### STANDARD #4- 80% TSS REMOVAL

ESTIMATED PROPOSED NEW PAVED COVER= 28,064S.F.

### REQUIRED WATER QUALITY VOLUME:

Required Treatment Volume	1.0	Inches Over Impervious Areas
Watershed Series	Paved Area	Water Quality Volume
P-1	13,258	1,104
P-2	12,229	1,015
P-3	2,577	2,332

The design of the drainage system is such that the site is routed through a series of treatment BMP's meeting the Standard. The attached TSS worksheets how the water treatment prior to the existing basin located on. No bypass is designed of the BMP's reducing the WQV.

Version 1, Automated: Mar. 4, 2008

<

2. Select BMP from Drop Down Menu

3. After BMP is selected, TSS Removal and other Columns are automatically completed

**TSS Removal Calculation Worksheet** Deep Sump and Hooded Stormceptor 450i Infiltration Basin Catch Basin BMP<sup>1</sup> W Location: Basin#1, Stafford Street Project: 20-385 TSS Removal Rate 0.00 0.00 0.80 0.80 0.25 0 Total TSS Removal = Starting TSS Load\* 0.03 0.03 0.15 0.75 1.00 Removed (C\*D) Amount 97% 0.00 0.00 0.12 0.60 0.25 Ш Separate Form Needs to Outlet or BMP Train be Completed for Each Remaining Load (D-E) 0.03 0.03 0.15 0.75 0.03 П

1. From MassDEP Stormwater Handbook Vol. 1 must be used if Proprietary BMP Proposed Non-automated TSS Calculation Sheet

Prepared By: pml

Date: 1/19/2021

which enters the BMP

\*Equals remaining load from previous BMP (E)

### **STANDARD #9- OPERATION & MAINTENANCE**

OPERATION & MAINTENANCE PLAN-

### **CURRENT OWNER & RESPONSIBLE PARTY:**

Matt Schold (Contractor shall be responsible during construction)

### **FUTURE OWNER & RESPONSIBLE PARTY:**

Matt Schold

### **DURING CONSTRUCTION:**

### SILT FENCE BARRIER:

The silt fence barrier shall be installed prior to construction.

During construction the contractor shall inspect the silt fence barrier on a weekly basis and after any significant rainstorm resulting in greater than 0.5" of rainfall. The barrier shall be inspected for any breaches or disturbed silt fence and repaired immediately.

After construction the barrier shall be maintained as stated above until all new areas are vegetated.

After construction these duties shall transfer to the property owner.

### CONSTRUCTION ENTRANCE APRONS:

Construction aprons shall be installed to protect Tractor Supply Parking Lot and Route 9. The construction entrance apron shall be installed prior to commencement of construction and shall be inspected weekly. The construction entrance apron shall be replaced when debris becomes noticeable on the existing pavement surfaces leading to and from the construction site.

### **SLOPE STABILIZATION:**

The slope stabilization controls shall be installed immediately upon obtaining final grades as shown on the project plans. Slopes in the swale area shall be stabilized according to the details provided. All 3:1 slopes established on-site shall be loamed and seeded as soon as weather permits. Any 2:1 slopes established shall be covered with slope stabilization fabric, then loamed and seeded as soon as weather permits. Areas in failure shall be re-graded to final grade and stabilized as necessary.

TEMPORARY BASINS:

The temporary basins shall be inspected immediately after storm events and cleaned to remove sediment build-up. Outfalls shall be inspected for erosion or scouring. Additional rip rap shall be added as required to minimize erosion.

### Proposed outlet control structures:

Outlet control structures at basins have temporary stone or other filtration device installed around inlet to prevent sediment deposits. Sediment shall be removed when accumulation exceeds 1" depth on paved surfaces.

### CHECK DAMS:

Check Dams shall be inspected weekly and after rainfall in excess of 0.5". Accumulated sediment shall be removed when depth exceeds 3" on the upstream sided of the dam. Stone or fabric shall be replaced when evidence of clogging is present.

### **CONSTRUCTION COMPLETION:**

The entire stormwater management system shall be inspected upon completion of construction. Portions of the system containing sediment shall be cleaned and all sediment properly removed.

### AFTER CONSTRUCTION:

### Existing CATCH BASINS:

At a minimum, the catch basins shall be inspected and cleaned on a quarterly basis. It is preferred that collection of accumulated sediment shall be accomplished by means of vacuum pumping and not by means of a clamshell bucket. Disposal of accumulated sediment shall be performed in accordance with applicable local, state, and federal guidelines and regulations.

### SEDIMENT BASINS

Sediment Basins shall be visually inspected monthly for accumulation of debris, slope failure, or stone displacement. Slopes shall be mowed quarterly. Bottom shall be swept, vacuumed of accumulated debris semi-annually.

### INFILTRATION BASIN

Inspect infiltration basin after major storm events (>3.0 inches) to verify stabilization and infiltration. Mow slopes, berms quarterly. Removed accumulated clippings from infiltration stone. Inspect basin semi-annually for the following:

Signs of differential settlement

- Cracking
- Erosion
- Leakage in embankments
- Tree growth on embankments
- Condition of rip rap
- Sediment accumulation
- Turf health.

### LONG TERM POLLUTION PREVENTION PLAN

The following are the material management practices that shall be used to reduce the risk of spills or other accidental exposure of materials and substances to stormwater runoff.

**Good Housekeeping**: The following good housekeeping practices will be followed on site during the construction project and continued upon completion of the construction activities.

- 1. A concerted effort shall be made to store only enough product required to complete a particular task.
- 2. All materials stored on site shall be stored in a neat and orderly fashion in their appropriate containers and, if possible, under a roof or other secure enclosure.
- 3. Products shall be kept in their original containers with the original manufacture's label.
- 4. Substances shall not be mixed with one another unless recommended by the manufacturer.
- 5. Whenever possible, all of a product shall be used up before disposing of the container.
- 6. Manufacture's recommendations for proper use and disposal shall be followed.
- 7. The site superintendent shall inspect daily to ensure proper use and disposal of materials on site.

**Hazardous Products**: The following practices are intended to reduce the risks associated with hazardous materials.

- 1. Products shall be kept in original containers unless they are not re-sealable.
- 2. Where feasible, the original label and material safety data shall be retained, whereas they contain important product information.
- 3. If surplus product must be disposed of, follow manufacturers or local and State recommended methods for proper disposal.

**Product Specific Practices:** The following product-specific practices shall be followed on site: Petroleum Products:

- 1. All on site vehicles shall be monitored for leaks and receive regular preventative maintenance to reduce the risk of leakage.
- 2. Petroleum products shall be stored in tightly sealed containers which are clearly labeled.
- 3. Petroleum Products shall be stored in compliance with Fire Marshall regulations.

### Bituminous Concrete:

Any bituminous concrete or asphalt substances used on site shall be applied according to the manufacturer's recommendations.

### Fertilizers:

Fertilizers shall be applied in the minimum amounts recommended by the manufacturer. Once applied, fertilizers shall be worked into the soil to limit exposure to stormwater. Storage shall be in a covered shed or trailer. The contents of any partially-used bags of fertilizer shall be transferred to a sealable plastic bag or bin to avoid spills

### Paints:

- 1. All containers shall be tightly sealed and stored when not required for use.
- 2. Excess paint shall not be discharged into any catch basin, drain manhole or any portion of the stormwater management system.
- 3. Excess paint shall be properly disposed of according to manufacturer's recommendations or State and local regulations.

### Concrete Trucks:

Concrete trucks shall not be allowed to wash out or discharge surplus concrete or drum wash water on site.

### SPILL CONTROL PRACTICES

In addition to the good housekeeping and material management practices discussed in the previous sections of this plan, the following practices shall be followed for spill prevention and cleanup:

- 1. Manufacturer's recommended methods for cleanup shall be readily available at the onsite trailer, and site personnel shall be made aware of the procedures and the location of the information.
- 2. Materials and equipment necessary for spill clean up shall be kept in the material storage area on site. Equipment and materials shall include, but not be limited to, brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust and plastic and metal trash containers specifically for this purpose.
- 3. All spills shall be cleaned up immediately after discovery.
- 4. The spill area shall be kept well ventilated, and personnel shall wear appropriate protective clothing to prevent injury from contact with hazardous substance.
- 5. Spills of toxic or hazardous material shall be reported to the appropriate State and/or local authority in accordance with local and/or State regulations.
- 6. The spill prevention plan shall be adjusted to include measures to prevent a particular type of spill from reoccurring and instructions on how to clean up the spill if there is another occurrence. A description of the spill, what caused it, and the clean up measures shall also be included.
- 7. The "Manager" shall be the spill prevention and cleanup coordinator. The "Manager" shall designate at least three other site personnel who will be trained in the spill control practices identified above.

### **APPENDICES:**

**Groundwater Mounding Calculation** 

Soil Logs and Soil Map Information

Inspection & Maintenance Logs During Construction

Inspection & Maintenance Logs After Construction

**Pre-Development Watershed Map** 

**Post-Developoment Watershed Map** 

### 21-146 -UG Pond 1 451 Worcester Road Ma HANTUSH GROUNDWATER MOUND CALCULATOR

This spreadsheet will calculate the height of a groundwater mound beneath a stormwater infiltration

Basin	Length	Width	Volume	Tit	ne	То	w (perc)	
	ft	ft	cf	start	end	Hrs	Days	ft/d
1	44	55.5	585	5	55	50	2.08	0.115

Head

0.29

0.36

di K (hyd. Conductivity)\* Texture m/d ft/d m/yr sand 5.55E+03 15.21 49.89 loamy sand 4.93E+03 13.51 44.31 sandy loam 1.09E+03 2.99 9.80 silty loam 2.27E+02 0.62 2.04 loam 2.19E+02 0.60 1.97 sandy clay loam 1.99E+02 0.55 1.79 silty clay loam 5.36E+01 0.15 0.48 clay loam 7.73E+01 0.21 0.69 sandy clay 6.84E+01 0.19 0.61

(b) = Width Plan View Plan View (a) = Length Vertical (w) Percolation 1 1 1 1 1 **Ground Level** Cross Section Increase in Maximum Hydraulic Head Hydraulic h<sub>i</sub> Initial Water Level

Source: Clapp and Hornberger (1978)

3.21E+01

4.05E+01

### Input Values

silty clay

clay


0.54	K	Horizontal hydraulic conductivity (feet/day)
0.200	Sy	Specific yield (dimensionless)
2.000	hi	Initial Water Level (feet)
44.000	а	Basin Length (feet)
55.500	b	Basin Width (feet)
0.1150	W	Recharge (infiltration) rate (feet/day)
2.083	t	duration of infiltration period (days)

0.09

0.11

3.198	h(max)	Maximum Hydraulic Head (feet)
1.198	Δh(max)	Maximum Groundwater Mound (feet)

Ground-water	Distance
Mound	from Center
(ft)	(ft)
1.198	0
1.153	15
0.017	30
0.000	45
0.000	60
0.000	75
0.000	90
0.000	105
0.000	120
0.000	135





V	A. Facility Information				
	Matt Schold				
	Owner Name				
	Stafford Street				
	Street Address		Map/Lot#		
	Leicester				
	City	State	Zip Code		
<b>m</b>	B. Site Information				
<del>-</del>	1. (Check one) New Construction	Upgrade			
5	Soil Survey Available?   Yes   No	If yes:	Mass. GIS Source		407B Soil Man Unit
	Charlton				
	Soil Name	Soil Limitations			
	Glacial Till	Ridge			
3	Soil Parent material Surficial Geological Report Available?	Landform No If ves:			
;			ource Map Unit		
	Description of Geologic Map Unit:				
4.	Flood Rate Insurance Map Within a regulatory floodway?	tory floodway?			
5.	Within a velocity zone?				
9	Within a Mapped Wetland Area?	☐ No If yes, MassG	If yes, MassGIS Wetland Data Layer:	Wetland Tyne	
7.	Current Water Resource Conditions (USGS):	August 2021 Month/Day/ Year	Range: 🛭 Above Normal	Normal	☐ Below Normal
œ.	Other references reviewed:				

# Commonwealth of Massachusetts City/Town of Leicester Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

	71-55-29 W	Longitude:	Slope (%)				70 feet	feet .	drock	er in Hole			Other					
area)	42-05-12 N	enna	boulders, etc.)			Position on Landscape (SU, SH, BS, FS, TS)	Wetlands	0	₹ock	110 Depth Standing Water in Hole		-	ist)					
posal	42	E C	, stones,			pe (SU, s			actured	110 Dep		Soil	(Moist)	0.11				
eserve dis	0		Surface Stones (e.g., cobbles, stones, boulders, etc.)			tion on Landsca		į					Soil Structure Consistence (Moist)					
nary and r	clear 80	many	Surface Stone			Posit	Drainage Way n/a feet	ell <u>n/a</u>		from Pit		Coarse Fragments % by Volume	Cobbles & Stones					
sed prin							ainage M	Water W	☐ FIII Material	36 Depth Weeping from Pit		Coarse % by	Gravel	N/A	N/A	N/A		
ry propos	8:30 Time	<u> </u>			Ridge	Landform	۵	Drinking		36 Dept	Soil Log	tures	Percent			25		
ired at ever	21	Wooded	Vegetation		涩	La		; ;	☐ Disturbed Soil	If yes:		Redoximorphic Features	Color			10YR5/8		
es requ	8-25-21	Calc	etc.)				n/a feet	10.00	II Yes:				Depth	N/A	N/A	36"		
C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)	er: 1 Hole#		(e.g., woodland, agricultural field, vacant lot, etc.)		_		Open Water Body	1788		<b>№</b>		Soil Matrix: Color-	Moist (Munsell)	10YR4/4	10YR4/6	5Y6/3		
ew (minim	Hole Numb		odland, agricultu	cation:	l: Glaical Till		Open	T	Present.	rved: 🛭 Yes		Soil Texture	(USDA	S.L.	S.L.	S.L.		
Site Revi	Deep Observation Hole Number: 1	Vacant		Description of Location:	Soil Parent Material:		Distances from:		4. Unsultable Materials Present: ☐ Tes 🖂 No	Groundwater Observed: ⊠ Yes		Soil Horizon	/Layer	AP	Bw	O O		
C. On-	Deep	-	I. Land Use	Des	2. Soil P		3. Distar	-	4. Unsulla	5. Groun		Confet (in)	repuii (iii)	0-10	10-28	28-120		



C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Dee	p Observati	Deep Observation Hole Number:	mber: 2		8-25-21	00:6	Ö	clear 80	42-5-12 N	12 N	71-55-29 W	
			Hok		Date	Time	\$	Weather	Latitude	Φ	l'ongitude.	
1 Land Use.		Vacant				Woodland		Some				
		(e.g., woodland, agricultural field, vacant lot, etc.)	gricultural field,	, vacant lot, e		Vegetation		Surface S	tones (e.g., cobble	Surface Stones (e.g., cobbles, stones, boulders, etc.)		
Des	Description of Location:	cation:									I	
Soil	Soil Parent Material	Chartlon Chartlon	u				Ridge					
:	מוכור ואמנס	<del>.</del>					Landform			Position on Landscape (SU, SH, BS, FS, TS)	SU, SH, BS, FS, TS)	
. Dista	Distances from:	Open Water Body		n/a feet		Drain	Drainage Way n/a feet	1/a feet	Wetla	Wetlands 70 feet		
oldetii iaul I	old.	Proper	Property Line 40	40 feet		Drinking Water Well n/a feet	ater Well n	1/a feet	Ö	Other feet		
Materia	als Present:	Materials Present:	No If Yes:		Disturbed Soil	☐ Fill Material		☐ Weathered	☐ Weathered/Fractured Rock	Bedrock		
. Groun	ndwater Obs	Groundwater Observed: ⊠ Yes	oN S	C		#	36" [	If yes: 36" Depth Weeping from Pit	om Pit	-	Vater in Hole	
						Soi	Soil Log					
Depth (in)		Soil Horizon Soil Texture	Soil Matrix:		Redoximorphic Features	77	Coarse %	Coarse Fragments % by Volume		Soil		
	iLayer	(USDA)	(Munsell)	Depth	Color	Percent	Gravel	Cobbles & Stones	Soil Structure	Consistence (Moist)	Other	
0-22	⋖	S.L.	10YR4/4	N/A								
22-32	В	S.L.	10YR6/6	N/A								
32-62	C1	S.L.	5Y6/3	36"	10YR5/8	25	N/A	N/A				
62-100	C2	L.S.	2.5Y5/4	N/A			N/A	N/A				
100-120	C3	S.L.	10YR4/4	N/A			N/A	N/A				
												T
V:+: 77 4	Additional Motor:											



## Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

. Determination of High Groundwater Elevation		
Method Used:	Obs. Hole #1	Obs. Hole #2
□ Depth observed standing water in observation hole	110 inches	110 inches
□ Depth weeping from side of observation hole	36 inches	36 inches
<ul> <li>□ Depth to soil redoximorphic features (mottles)</li> </ul>	36 inches	36 inches
<ul> <li>□ Depth to adjusted seasonal high groundwater (S<sub>h</sub>)</li> <li>(USGS methodology)</li> </ul>	inches	inches
Index Well Number Reading Date		
$S_h = S_c - [S_r \times (OW_c - OW_{max})/OW_r]$		
Obs. HoleWell# S <sub>c</sub> S <sub>r</sub>	OW <sub>c</sub>	OW <sub>max</sub> OW <sub>r</sub>

က်

### E. Depth of Pervious Material

inches

2. Estimated Depth to High Groundwater:

- 1. Depth of Naturally Occurring Pervious Material
- absorption a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil system?

<ul><li>✓ Yes ☐ No</li><li>If yes, at what depth was it observed (exclude A and O</li></ul>	Upper boundary:	28	Lower boundary:	120	
		inches		inches	
c. If no, at what depth was impervious material observed?	Upper boundary:		Lower boundary:		

inches

inches



## Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

### F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through 15.107.

Peter Lavoie	8/25/21
Signature of Soil Evaluator	Date
Peter Lavoie #1332	2023
Typed or Printed Name of Soil Evaluator / License #	Expiration Date of License
Shelley Hammond	Leicester
Name of Approving Authority Witness	Approving Authority

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with Percolation Test Form 12.

Field Diagrams: Use this area for field diagrams:



A. Facility Information

	Matt Schold				
	Owner Name				
73.50	Stafford Street				
	Street Address		Map/Lot #		
	Leicester	MA			
N <del></del> .	City	State	Zip Code		
m	B. Site Information				
	1. (Check one) 🛭 New Construction	☐ Upgrade ☐ Repair			
oi	Soil Survey Available? 🛛 Yes 📋 No	o If yes:	<b>⊠</b>  ∂	Mass. GIS 407B	7B Moo llost
	Charlton		5		Soli Map Offic
Lāš	Soil Name	Soil Limitations			
	Glacial Till	Ridge			
~i	Soil Parent material Surficial Geological Report Available?	Landform No If yes:	Voar Dihlichad/Source	##E	
1				Map Unit	
	Description of Geologic Map Unit:				
	Flood Rate Insurance Map Within a re	Within a regulatory floodway?	oN ⊠		
	Within a velocity zone?	0			
·	Within a Mapped Wetland Area?	No ⊠	If yes, MassGIS Wetland Data Layer:	r: Wetland Tuno	
	Current Water Resource Conditions (USGS):	August 2021 Month/Day/ Year	Range: 🛛 Above Normal		☐ Below Normal
~·	Other references reviewed:				



	M 60		(9)					et											
2	71-55-29 W	Longitude:	Slope (%)		Position on Landscape (SU, SH, BS, FS, TS)	70 feet	feet		116 Depth Standing Water in Hole		Other								
	5-12 N	de	oulders, etc.)			Wetlands	Other					e ()							
sposal a	42-0	Latitude	s, stones, bo			ape (SU, SF			☐ Disturbed Soil ☐ Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock	If yes: 38 Depth Weeping from Pit		Soil	(Moist)						
eserve dis	0		Surface Stones (e.g., cobbles, stones, boulders, etc.)			ion on Landsca	Drainage Way <u>n/a</u> feet					6	Soil Structure Consistence (Moist)						
to holes required at every proposed primary and reserve disposal area)	clear 80	weather				Posi		Drinking Water Well n/a feet				Coarse Fragments % by Volume	Cobbles & Stones						
sed prin													Gravel	N/A	N/A	N/A	N/A	N/A	
ry propo	9:30	Time			Ridge	Landform		Drinking		38 Dep	Soil Log	itures	Percent			25			
equired at every	2	Wooded	Vegetation		~	La				If yes		Redoximorphic Features	Color			10YR5/8			
es requ	8-25-2	Dale				n/a feet	40 feet	If Yes:				Depth	N/A	N/A	38"	N/A	N/A		
iew (minimum of two ho	er: 3	± 000	(e.g., woodland, agricultural field, vacant lot, etc.)	oodiand, agricultural field, vacant lot, e cation:		li: Glaical Till	Open Water Body		_	Groundwater Observed: ☒ Yes ☐ No		Soil Matrix: Color-	Moist (Munsell)	10YR4/4	10YR4/6	576/3	2.5Y5/4	5Y6/3	
	Hole Numb						Open	-				Soil Texture	(USDA	S.L.	S.L.	S.L.	L.S.	S.L.	
Site Revi	Observation	Vacant		Description of Location:	Soil Parent Material:		Distances from:		ble Materials	dwater Obse		Soil Horizon	/Layer	АР	Bw	C1	C2	င္သ	
C. On-	Deep		I. Land Use	Des	2. Soil Pa		3. Distan		I. Unsuita	5. Groun		Capth (in)	(iii)	0-18	18-36	36-62	62-100	100-120	

Additional Notes:



C. On- Deep	Site Rev Observation	On-Site Review (minimum Deep Observation Hole Number:	um of two	holes re	required a 8-25-21	it every p 10:00	proposed	d primary and clear 80	C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)  Deep Observation Hole Number: 4 8-25-21 10:00 clear 80 42-5-12 N	sposal area) 2 N	71-55-29 W
1 pnd I ko.		Vacant	# Hole #		Date Wo	Time Woodland	Š	Weather	Latitude		Longitude:
		(e.g., woodland, agricultural field, vacant lot, etc.)	cultural field, va	cant lot, etc		Vegetation		Surface Sto	nes (e.g., cobbles	Surface Stones (e.g., cobbles, stones, boulders, etc.)	Slope (%)
Desci	Description of Location:	ation:									Ť
Soil P	Soil Parent Material:	Chartlon					Ridge				
							Landform			Position on Landscape (SU, SH, BS, FS, TS)	(SU, SH, BS, FS, TS)
3. Distar	Distances from:	Open Water Body	Body n/a feet	feet		Drair	Drainage Way n/a feet	n/a feet	Wetla	Wetlands 70 feet	
4 Unsuitable	old	Property Line	/ Line 40 feet	feet	_	Orinking W	Drinking Water Well n/a feet	n/a feet	ō	Other feet	
Materia	Is Present:	Materials Present: X Yes No	lo If Yes:	☐ Disturbed Soil		Fill Material		☐ Weathered/	☐ Weathered/Fractured Rock	Bedrock	
5. Groun	dwater Obse	Groundwater Observed: ⊠ Yes	% □				3: 43"	If yes: 43" Depth Weeping from Pit	om Pit		Water in Hole
						So	Soil Log				
Depth (in)	Soil Horizon	Soil Texture	Soil Matrix:	Redox	Redoximorphic Features	atures	Coarse % by	Coarse Fragments % by Volume	10 110	Soil	
	iLayer	(USDA)	(Munsell)	Depth	Color	Percent	Gravel	Cobbles & Stones	ooii orructure	(Moist)	Other
0-43	Ē										
43-58	C1	S.L.	£/9,43	43"	10YR5/8	25					
58-120	C2	L.S.	2.575/4	N/A			N/A	N/A			
Additio	Additional Motos:										

Additional Notes:



D. Determination of High Groundwater Elevation	tion		
<ol> <li>Method Used:</li> <li>Depth observed standing water in observation hole</li> </ol>	Obs. Hole $#3$ 116 inches	Obs. Hole # <u>4</u> <u>118</u> inches	
Depth weeping from side of observation hole	38 inches	43 inches	
<ul> <li>☑ Depth to soil redoximorphic features (mottles)</li> <li>☑ Depth to adjusted seasonal high groundwater (Sh)</li> <li>(USGS methodology)</li> </ul>	38 inches inches	43 inches inches	
Index Well Number $S_h = S_c - [S_r \times (OW_c - OW_{max})/OW_r] \label{eq:Sh}$			
Obs. Hole/Well# S <sub>c</sub> S <sub>r</sub>	OW <sub>c</sub>	OW <sub>max</sub> OW <sub>r</sub>	ng,
2. Estimated Depth to High Groundwater: inches			
E. Depth of Pervious Material			
1. Depth of Naturally Occurring Pervious Material			
<ul> <li>a. Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil system?</li> </ul>	ial exist in all areas observ	ed throughout the area proposed for	the soil absorption
<ul><li>b. If yes, at what depth was it observed (exclude A and O Horizons)?</li></ul>	Upper boundary:	43 Lower boundary:	120 inches

inches

Lower boundary:

inches

Upper boundary:

c. If no, at what depth was impervious material observed?




# F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through

Expiration Date of License Approving Authority Leicester 8/25/21 2023 Date Typed or Printed Name of Soil Evaluator / License # Name of Approving Authority Witness 15.107. Peter Lavoie Signature of Soil Evaluator Peter Lavoie #1332 Shelley Hammond

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with Percolation Test Form 12.

Field Diagrams: Use this area for field diagrams:




# MAP LEGEND

### Very Stony Spot Stony Spot Spoil Area Wet Spot Other W 8 600 0 Soil Map Unit Polygons Area of Interest (AOI) Soil Map Unit Lines Soil Map Unit Poin Special Point Features Area of Interest (AOI) -Soils

	al Line Features	
	Speci	eatures
)	1	Water Fe
ıts		

Borrow Pit		
	Transportation	tation
ciay spot	1	Rails
Closed Depression	}	Interstate Highways
Gravel Pit	5	US Routes
Gravelly Spot	Ú	Major Roads



Marsh or swamp

Lava Flow

Landfill

Mine or Quarry

Miscellaneous Water

Perennial Water

Rock Outcrop

# Please rely on the bar scale on each map sheet for map measurements.

Streams and Canals

**Borrow Pit** 

Blowout

9

line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil

Warning: Soil Map may not be valid at this scale.

The soil surveys that comprise your AOI were mapped at

MAP INFORMATION

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

distance and area. A projection that preserves area, such as the Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Worcester County, Massachusetts, Southern

Survey Area Data: Version 14, Sep 3, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Date(s) aerial images were photographed: Apr 8, 2011—Jul 9,

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Severely Eroded Spot

Sandy Spot Saline Spot

Slide or Slip

A

Sinkhole

Sodic Spot

### **Map Unit Legend**

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
1	Water	0.8	0.1%
52A	Freetown muck, 0 to 1 percent slopes	27.5	4.4%
71A	Ridgebury fine sandy loam, 0 to 3 percent slopes, extremely stony	8.0	1.3%
71B	Ridgebury fine sandy loam, 3 to 8 percent slopes, extremely stony	3.0	0.5%
73A	Whitman fine sandy loam, 0 to 3 percent slopes, extremely stony	16.3	2.6%
102C	Chatfield-Hollis-Rock outcrop complex, 0 to 15 percent slopes	37.6	6.0%
102E	Chatfield-Hollis-Rock outcrop complex, 15 to 35 percent slopes	3.7	0.6%
305B	Paxton fine sandy loam, 3 to 8 percent slopes	19.1	3.0%
307C	Paxton fine sandy loam, 8 to 15 percent slopes, extremely stony	15.5	2.5%
315B	Scituate fine sandy loam, 3 to 8 percent slopes	2.0	0.3%
407B	Charlton fine sandy loam, 3 to 8 percent slopes, extremely stony	16.3	2.6%
420B	Canton fine sandy loam, 3 to 8 percent slopes	122.4	19.5%
420C	Canton fine sandy loam, 8 to 15 percent slopes	45.8	7.3%
422B	Canton fine sandy loam, 0 to 8 percent slopes, extremely stony	213.6	34.1%
422C	Canton fine sandy loam, 8 to 15 percent slopes, extremely stony	90.5	14.4%
422E	Canton fine sandy loam, 15 to 35 percent slopes, extremely stony	4.5	0.7%
Totals for Area of Interest		626.7	100.0%

### Worcester County, Massachusetts, Southern Part

### 420C—Canton fine sandy loam, 8 to 15 percent slopes

### **Map Unit Setting**

National map unit symbol: 2w817

Elevation: 0 to 1,330 feet

Mean annual precipitation: 36 to 71 inches Mean annual air temperature: 39 to 55 degrees F

Frost-free period: 140 to 240 days

Farmland classification: Farmland of statewide importance

### **Map Unit Composition**

Canton and similar soils: 80 percent Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

### **Description of Canton**

### Setting

Landform: Hills, moraines, ridges

Landform position (two-dimensional): Summit, shoulder, backslope Landform position (three-dimensional): Nose slope, crest, side slope

Down-slope shape: Convex, linear Across-slope shape: Convex

Parent material: Coarse-loamy over sandy melt-out till derived from

gneiss, granite, and/or schist

### Typical profile

Ap - 0 to 7 inches: fine sandy loam Bw1 - 7 to 15 inches: fine sandy loam

Bw2 - 15 to 26 inches: gravelly fine sandy loam 2C - 26 to 65 inches: gravelly loamy sand

### Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: 19 to 39 inches to strongly contrasting

textural stratification

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 14.17 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Available water supply, 0 to 60 inches: Very low (about 2.7 inches)

### Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: B

Ecological site: F144AY034CT - Well Drained Till Uplands

Hydric soil rating: No

### **Minor Components**

### Montauk

Percent of map unit: 6 percent

Landform: Moraines, ground moraines, hills, drumlins Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex, linear Across-slope shape: Convex Hydric soil rating: No

### Scituate

Percent of map unit: 6 percent

Landform: Hills, drumlins, ground moraines

Landform position (two-dimensional): Backslope, footslope

Landform position (three-dimensional): Side slope

Down-slope shape: Convex, linear Across-slope shape: Convex Hydric soil rating: No

### Charlton

Percent of map unit: 4 percent

Landform: Ridges, ground moraines, hills Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex, linear Across-slope shape: Convex Hydric soil rating: No

### Newfields

Percent of map unit: 4 percent

Landform: Ground moraines, hills, moraines Landform position (two-dimensional): Footslope Landform position (three-dimensional): Base slope

Down-slope shape: Linear Across-slope shape: Concave

Hydric soil rating: No

### **Data Source Information**

Soil Survey Area: Worcester County, Massachusetts, Southern Part

Survey Area Data: Version 14, Sep 3, 2021

### Inspection and Maintenance Log AFTER CONSTRUCTION

FOR: Stafford Street & After 3.0" Rain

Components				Date
UG Basin#1				
- twice a year				
Comments during insp.				
Note corrective measures				
performed & Date				
Settling Basin				
-twice a year				
Comments during insp.				
N-4-	£			
Note corrective measures				
performed & date				
Rip Rap Swale				
-twice a year				
Comments during insp.				
Note				
Note corrective measures performed & date				
Stormceptor #1				
-twice a year				
Comments during insp.				TANKE THE SECOND
Note corrective measures				
performed & date				
Catch Basins				
- 8 inches of sediment or twice a year				
Comments during insp.				
Note corrective measures	N			
performed & date				
	Inspector	Title	Date	
	Address	T	el#	

### Inspection and Maintenance Log AFTER CONSTRUCTION

FOR: Stafford Street & After 3.0" Rain

Components				Date
Stormceptor #2				Date
-8 inches of sediment or twice a year				
Comments during insp.				
Note corrective measures				
performed & date				
Outlet Control Structure				
Twice a year				
Comments during insp.				
Note corrective measures	3.40			
performed & date				
Drain Manholes				
-four times a year				
Comments during insp.				
Note corrective measures				
performed & date				
Spillway at settling basin -as-needed				
Comments during insp.				
Note corrective measures				-
performed & date				
Gutters on Building				
as needed				
Comments during insp.				
Note corrective measures				
performed & date				
All Flared end sections and rip rap aprons				
- twice a year				
Comments during insp.				
Note corrective measures				
erformed & date				
	Inspector	Title	Date	
Components				Date
				Daic

## WEEKLY Inspection and Maintenance Log DURING CONSTRUCTION

FOR: Stafford St & After 0.5" Rain

Components				Date
Erosion Control – Weekly		-		Date
Comments during insp.				
N				
Note corrective measures				
performed & Date				
On Site Pavement				
Sweeping – as Needed				
Comments during insp.				
Note corrective measures		1		
performed & date				
an T				
Silt Fence & Composite Sock- Monthly				
Comments during insp.				
Note corrective measures				
performed & date				
Towns and P			The second secon	
Temporary Basin Area as Needed				
Comments during insp.				
Note corrective measures				
performed & date				
performed & date				
Construction Entrance				_
as Needed				
Comments during insp.				
Note corrective measures				
performed & date			<u> </u>	
	Inspector	Title	Date	
	Address	т	el#	
	Addicas	1	C1#	

### WEEKLY Inspection and Maintenance Log DURING CONSTRUCTION

FOR: Stafford St & After 0.5" Rain

Components				Date
Notify Cons. Comm. Issues				Date
effecting Resource Areas				
Comments during insp.				
N				
Note corrective measures				
performed & date				
Silt of Public (Charlton Road)				
Streets - Daily				
Comments during insp.				
N. 4				
Note corrective measures				
performed & date				
Stockpile Materials				
Ring with Composite Sock – Weekly Comments during insp.				
Comments during hisp.				
Note corrective measures				
performed & date				
Any Spill Fuel, Chemical-				
Daily				
Comments during insp.				
Note corrective measures				
performed & date				
Temporary Ground	and the second s			
Cover Area – Weekly				
Comments during insp.				
Note course.				
Note corrective measures performed & date				
Temporary Stone at				
Access Drive as Needed				
Comments during insp.				
Comments during insp.				
Note corrective measures				
performed & date				
	Inspector	Title	Date	
	Address	Γ	Tel#	

## WEEKLY Inspection and Maintenance Log DURING CONSTRUCTION

FOR: Stafford St & After 0.5" Rain

Components			Date
Lawn Area / Mulch Area	100000000000000000000000000000000000000	300000000000000000000000000000000000000	Date
Erosion, Washouts			
Comments during insp.			
NT-4-			
Note corrective measures performed & date			
Stone Aprons at Outfalls Exit			
as Needed			
Comments during insp.			
aumg mop.			
Note corrective measures			
performed & date			
Forebay			
as Needed			
Comments during insp.			
Note corrective measures			
performed & date			
performed & date	W.		
		-	
Basins 1			
as Needed			
Comments during insp.			
N			
Note corrective measures performed & date			
Illicit Drainage Discharge			
Comments during insp.			
comments during map.			
Note corrective measures			
performed & date			
	Inspector	Title	Date
	Address	Te	1#